

SE/South Circle. Agt. No.60/2022-2023

FILE No. DB/SC/2589/2021

REPORT ACCOMPANYING SLIP FOR LUMP SUM AGREEMENT
(FOR OFFICE USE ONLY)

TAMILNADU POLICE HOUSING CORPORATION LTD.,
SOUTH CIRCLE, MADURAI – 625 014.

NAME OF PROJECT	:	Forensic Sciences Department – Development of infrastructure and Laboratory ambience at Regional Forensic Science Laboratories at Madurai and Trichy towards establishment of Computer Forensics Divisions
NAME OF WORK	:	Providing additional infrastructure facilities for the proposed Computer Forensic Laboratory at Regional Forensic Science Laboratory MADURAI in Madurai District
ESTIMATE AMOUNT	:	₹ 26,10,500/-
ESTIMATE No.	:	SE SC.ER.No.21/2022-2023
ESTIMATE AMOUNT PUT IN TENDER	:	₹ 24,80,453.44 (2022-2023) (Including the GST @12%)
TENDER VALUE	:	₹ 24,00,047.94 (Including the GST @12%)
LESS AMOUNT	:	(-) ₹ 80,405.49
LESS PERCENTAGE	:	(-) 3.24%
TENDER ACCEPTED BY WHOM	:	The Superintending Engineer, TNPHC Ltd., South Circle, Madurai -14
NAME OF THE CONTRACTOR	:	M/s.G.N.Builders
No. OF ITEMS IN THE AGREEMENT	:	55 (Fifty five Only)
No. OF PAGES IN THE AGREEMENT	:	64 (Sixty four only)
No. OF CORRECTIONS IN THE AGREEMENT	}	Nil


29.08.2022
SUPERINTENDING ENGINEER
SOUTH CIRCLE, TNPHC LTD.,



தமிழ்நாடு தமிலநாடு TAMILNADU
29 AUG 2022

G.N. பிஸ்டர்ஸ்
நாகர்கோவில்

CR 804605
T. Meenakshi Bharathi
T. சோமசுந்தரி
முத்திரைத்தாள் விற்பனையாளர்
19/3, கரவன் தெருள்,
கோகலே ரோடு, மதுரை-2
RC. No. 1761 / B1 / 97-17

TAMIL NADU POLICE HOUSING CORPORATION LIMITED,
SOUTH CIRCLE, MADURAI – 625 014.

ARTICLES OF AGREEMENT

ARTICLES OF AGREEMENT made this 29th day of August 22

BETWEEN the Tamil Nadu Police Housing Corporation Limited, (hereinafter called the Corporation Limited which expression shall where the context so admits include its successors in office and assigns) of the ONE PART and

**M/s.G.N.BUILDERS,
174A/762, RAJAKKAMANGALAM ROAD,
KEELAKONAM,
NAGERCOIL.**

(Hereinafter called the contractor which expression shall where the context so admits include its heirs, executors, administrators and legal representatives) of the OTHER PART

For G.N.BUILDERS

[Signature]

No. of corrections

Superintending Engineer/ South Circle .

[Signature]
24.8.22

TAMIL NADU POLICE HOUSING CORPORATION LIMITED.,
SOUTH CIRCLE, MADURAI - 625 014.

ARTICLES OF AGREEMENT

ARTICLES OF AGREEMENT made this _____ day of _____
BETWEEN the Tamil Nadu Police Housing Corporation Limited, (hereinafter called the Corporation Limited which expression shall where the context so admits include its successors in office and assigns) of the ONE PART and

**M/s.G.N.BUILDERS,
174A/762, RAJAKKAMANGALAM ROAD,
KEELAKONAM,
NAGERCOIL.**

(Hereinafter called the contractor which expression shall where the context so admits include its heirs, executors, administrators and legal representatives) of the OTHER PART


WHEREAS the corporation Limited is desirous of **Providing additional infrastructure facilities for the proposed Computer Forensic Laboratory at Regional Forensic Science Laboratory Madurai in Madurai District** and have caused an estimate of probable quantities contained in schedule A, drawings and specifications describing the work to be done to be prepared.


AND WHEREAS the said schedule A, drawings (schedule B) and the specifications (schedule C) and other schedules herewith annexed have been signed by or on behalf of the parties hereto.

AND WHEREAS the contractor have agreed to the retention, by the Corporation Limited of earnest money (with GST) of **₹22,100/- (Rupees twenty two thousand and one hundred only) in the form of Demand Draft No.829397 Dated:02.08.2022 issued by Indian Overseas Bank, GPT KONAM, 1762, Nagercoil-4** paid by them when they submitted their tender, as security for the due fulfillment of the contract to the satisfaction of the Corporation Limited or any other officer authorized by the Corporation Limited.

For G.N.BUILDERS


Contractor


No. of corrections


Superintending Engineer/South Circle.

22

AND WHEREAS the Contractor have remitted a further sum of ₹28,000/- (Rupees twenty eight thousand only) paid in the form of Demand Draft No: 924916 Dated: 29.08.2022 issued by Indian Overseas Bank, Chokkikulam-0018 against the balance of the security deposit amount ₹26,000/- (with GST) for the due fulfillment of the contract to the satisfaction of the Corporation Limited or any other officer authorized by the Corporation Limited.

AND WHEREAS the Contractor have also signed a copy of the Tamilnadu Building practice and the addenda volume there to maintained in the office of the Superintending Engineer /South Circle Tamil Nadu Police Housing Corporation Limited in acknowledgement of being bound by all the conditions of the clauses of the general conditions of contract and all the standard specifications for items of works described by a standard Specification number in Schedule – A.


AND WHEREAS the contractor have agreed to execute upon and subject to the conditions set forth in the conditions of contract of the Tamil Nadu Building Practice and such other conditions as are contained in all the specifications forming part of this contract (hereinafter referred to as “the said conditions”) the work shown upon the drawings and described in the said specifications and set forth in Schedule –A as the “Probable Quantities” and comply with the rate of progress noted at the end of this ARTICLES OF AGREEMENT, for a sum of ₹ 24,00,047.94 (Rupees twenty four lakhs and forty seven and paise ninety four only) or such other sum as may be arrived at under the clause of the General conditions of contract relating to “Payment on lumpsum basis or by final measurement at Unit Prices”


Now it is hereby agreed as follows:

1. In consideration of the payment of the said sum of ₹ 24,00,047.94 (Rupees twenty four lakhs and forty seven and paise ninety four only) or such other sum as may be arrived at under the clause of the General conditions of contract relating to Payment on lumpsum basis or by final measurement at unit prices, the contractor will upon and subject to the said conditions execute and complete the works shown upon the said drawings and described in the said specifications and to the extent of the probable quantities shown in schedule A, with such variations by way of alterations of, additions to, or deductions from, the said works and method of payment there for are as provided for in the said conditions.

For G.N.BUILDERS


Contractor


No. of corrections


Superintending Engineer/South Circle .

2. The term "Corporation Limited" in the said conditions shall mean the Tamil Nadu Police Housing Corporation Limited or any officer of the Corporation Limited incharge of the works who shall be competent to exercise all the powers and privileges reserved herein, in favour of the Corporation Limited with the previous sanction of the Corporation Limited or any other officer authorized by the Corporation Limited.
3. The arbitrator for fulfilling the duties set forth in the arbitration clause of the General conditions of contract shall be the Chief Engineer, Tamil Nadu Police Housing Corporation Limited upto value of claims of Rs. 50,000/- If the value of claims exceeds Rs. 50,000/- the matter shall be referred to the court having jurisdiction over Tamil Nadu state.
4. Time shall be considered as the essence of the agreement and the Contractor hereby agrees to commence the work as soon as this agreement is accepted by the Corporation Limited or any other officer authorized by the Corporation Limited and the site (or premises) is handed over to them as provided for in the said conditions and agrees to complete the work within **SIX** months from the date of such handing over the site (or premises) and to show progress as defined in the tabular statement "RATE OF PROGRESS" below, subject nevertheless to the provisions for extension of time contained in clause 56 of the General conditions of contract.

Rate of Progress


The following rate of progress and proportionate value of work done from time to time, as will be indicated by the Executive Engineer's Certificate of the value of work done will be required.


Date of commencement of this programme will be the date on which the site (or premises) is handed over to the Contractor.

Period after date of Commencement (1)	Percentage of work completed (Based on Contract lumpsum amount) (2)
I - Month	15% ✓
II - Month	30% ✓
III - Month	45% ✓
IV - Month	60% ✓
V - Month	80% ✓
VI - Month	100% ✓

For G.N.BUILDERS


Contractor


No. of corrections


Superintending Engineer/South Circle .

5. "The said conditions " shall be read and construed as forming part of this agreement and the parties hereto will respectively abide by and submit themselves to the conditions and stipulations and perform the agreements on their parts, respectively.

6. Upon the terms and conditions of this agreement being fulfilled and performed to the satisfaction of the Corporation Limited or any other officer authorized by the Corporation Limited, the security deposited by the contractor as herein before recited or such portion thereof as they may be entitled to under the said conditions shall be returned to the contractor.

IN WITNESS WHERE OF the contractor **M/s.G.N.BUILDERS**, have hereunto set their hand and the Superintending Engineer/South Circle of Tamil Nadu Police Housing Corporation Limited on behalf of the Corporation Limited have hereunto set their hand, the day and year first above written.

Signed by the Contractor : **For G.N.BUILDERS**

[Signature] X

Address : **M/s.G.N.BUILDERS,
174A/762, RAJAKKAMANGALAM ROAD,
KEELAKONAM,
NAGERCOIL.** X

For G.N.BUILDERS

[Signature]
Contractor

[Signature]
No. of corrections

[Signature]
Superintending Engineer/South Circle .

TAMIL NADU POLICE HOUSING CORPORATION LIMITED

No.1, INSPECTOR QUARTERS, TSP 6 TH BATTALION CAMPUS,
NEW NATHAM ROAD, MADURAI - 625014.

Schedule 'A'

- A. The quantities given here are those upon which the lumpsum tender cost of the work is based, but they are subject to alterations, omissions, deductions or additions are provided for in the conditions of this contract and do not necessarily show the actual quantities of work to be done. The unit rates excluding GST amount quoted are those governing payments for extras or deductions or omissions according to the conditions of the contract asset forth in the general conditions of the contract of the Tamil Nadu Building practice and other conditions or specifications of this contract.
- B. It is to be expressly understood that the measured work is to be taken net (not withstanding any custom of practice to the contrary) according to the actual quantities when in place and finished according to the drawing or as may be ordered from time to time by the Chief Engineer and the cost calculated-by measurement or Weight at the respective prices without any additional charges for any necessary or contingent works connected herewith. The rates quoted excluding GST amount are for works in situ and complete in every respect.
- C. Unavoidable delays may entail in rate instances, for delays beyond 3 months after execution of agreement, offer may be with drawn/cancelled, validity shall be however optional subject to mutual consent by the contractor and TNPHC at agreed rates without extras.
- D. As a result of continuous improvements contemplated by the TNPHC in layouts/type design, substantial variations might occur in one more items. The tenderer will be expected to adopt such modifications whenever necessitated and ordered for.
- E. If rarely owing to non availability of vacant lands in the site mentioned in the notification change of site either partly or wholly is warranted, the tenderer shall accept to execute work accordingly as may be necessitated and ordered for at agreed rates or derived rates.

For G.N.BUILDERS

CONTRACTOR

NO. OF CORRECTIONS

SUPERINTENDING ENGINEER/SOUTH CIRCLE

SCHEDULE - A

NA. OF WORK : PROVIDING ADDITIONAL INFRA STRUCTURE FACILITIES FOR THE PROPOSED COMPUTER FORENSIC LABORATORY AT REGIONAL FORENSIC SCIENCE LABORATORY MADURAI IN MADURAI DISTRICT

S.NO	QUANTITY	DESCRIPTION OF WORK	RATE EXCLUSIVE OF GST IN FIGURES AND IN WORDS	UNIT IN FIGURES AND IN WORDS	AMOUNT
1	2	3	4	5	6
1	3.73 Cu.M.	DISMANTLING CLEARING AWAY AND CAREFULLY STACKING MATERIALS USEFUL FOR REUSE OF BRICK MASONRY IN CEMENT MORTAR WALLS WITHOUT AFFECTING THE ADJACENT STRUCTURES, INCLUDING THE COST OF REQUIRED TOOLS AND PLANTS AND SCAFFOLDING IF NECESSARY AND CLEARING THE DISMANTLED MATERIALS AWAY FROM THE SITE ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. a) UNDER 3.00 M HT	Rs.250.00 (Rupees two hundred and fifty only)	1.Cu.M. (ONE CUBIC METRE)	932.50
2	0.86 Cu.M.	DISMANTLING CLEARING AWAY AND CAREFULLY STACKING MATERIALS USEFUL FOR RE-USE OF REINFORCEMENT CEMENT CONCRETE WITHOUT AFFECTING THE ADJACENT STRUCTURES, INCLUDING THE COST OF REQUIRED TOOLS AND PLANTS AND SCAFFOLDING IF NECESSARY AND CLEARING THE DISMANTLED MATERIALS AWAY FROM THE SITE ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS.	Rs.6400.00 (Rupees six thousand and four hundred only)	1.Cu.M. (ONE CUBIC METRE)	5504.00
3	11.56 Sq.M.	CLEAN REMOVAL OF FLOOR FINISH AND DADOING WALLS IN CEMENT MORTAR WITH MOSAIC TILES / GLAZED TILES / CUDDAPPAH SLAB WITHOUT AFFECTING THE ADJACENT STRUCTURES, INCLUDING THE COST OF REQUIRED TOOLS AND PLANTS AND SCAFFOLDING IF NECESSARY AND CLEARING THE DEBRIS AWAY FROM THE SITE ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS.	Rs.50.00 (Rupees fifty only)	1.Sq.M. (ONE SQUARE METRE)	578.00
4	465.67 Sq.M.	DISMANTLING CLEARING AWAY AND CAREFULLY STACKING MATERIALS USEFUL FOR RE-USE OF PRESSED TILES IN CEMENT MORTAR AND WITHOUT AFFECTING THE ADJACENT STRUCTURES, INCLUDING THE COST OF REQUIRED TOOLS AND PLANTS AND SCAFFOLDING IF NECESSARY ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS.	Rs.25.00 (Rupees twenty five only)	1.Sq.M. (ONE SQUARE METRE)	11641.75
5	11.80 Sq.M.	SUPPLYING AND FIXING OF VETRIFIED TILES OF BEST APPROVED QUALITY (IVORY) 600X600X8MM FOR FLOORING AND OTHER SIMILAR WORKS (THE COLOUR AND SHADE SHALL BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USING) OVER CEMENT MORTAR 1:3 (ONE OF CEMENT AND THREE OF CRUSHED STONE SAND) 20MM THICK INCLUDING FIXING IN POSITION CUTTING THE TILES TO THE REQUIRED SIZE WHEREVER NECESSARY POINTING THE JOINTS WITH GROUT (TILE JOINT FILLER) CURING FINISHING ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS.	Rs.1400.00 (Rupees one thousand and four hundred only)	1.Sq.M. (ONE SQUARE METRE)	16520.00
					35176.25

For G.N.BUILDERS

G. N. Builders
CONTRACTOR

NO. OF CORRECTIONS

SUPERINTENDING ENGINEER/SOUTH CIRCLE.

S.NO	QUANTITY	DESCRIPTION OF WORK	RATE EXCLUSIVE OF GST IN FIGURES AND IN WORDS	UNIT IN FIGURES AND IN WORDS	AMOUNT
1	2	3	4	5	6
					35176.25
6	4.70 Sq.M.	SUPPLYING AND FIXING OF COLOUR GLAZED TILES OF BEST APPROVED QUALITY (THE COLOUR AND SHADE SHALL BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USING) OVER CEMENT PLASTERING IN CM 1:2 (ONE OF CEMENT AND TWO OF CRUSHED STONE SAND) 10MM THICK INCLUDING FIXING IN POSITION, CUTTING THE TILES TO THE REQUIRED SIZE WHEREVER NECESSARY, POINTING THE JOINTS WITH GROUT (TILE JOINT FILLER) , CURING, FINISHING ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE BRAND AND QUALITY OF TILES SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE).	Rs.1300.00 (Rupees one thousand and three hundred only)	1.Sq.M. (ONE SQUARE METRE)	6110.00
7	56.60 Sq.M.	WHITE WASHING THREE COATS USING CLEAN SHELL LIME SLAKED INCLUDING COST OF LIME, GUM, BLUE, BRUSHES, INCLUDING SCAFFOLDING ETC., COMPLETE IN ALL RESPECTS.	Rs.32.00 (Rupees thirty two only)	1.Sq.M. (ONE SQUARE METRE)	1811.20
8	35.00 Sq.M.	SUPPLYING, FABRICATING AND FIXING IN POSITION OF ALUMINIUM PARTITION WITH BOTTOM 2/3 PANELED 12MM THICK NOVAPAN SHEET AND TOP 1/3 PLAIN GLASS 5.5MM THICK TO FIT AGAINST THE PARTITION WALL. THE OUTER FRAME TOP AND BOTTOM USING RECTANGULAR BOX SECTION NO.9221 OF SIZE 101.50X44.450X2MM AT WEIGHT OF 1.975 KG/M VERTICAL AS WELL AS HORIZONTAL USING RECTANGULAR BOX SECTION NO.9222 OF 63.50X38.10X2MM AT WEIGHT OF 1.174 KG/M WITH ACCESSORIES INCLUDING COST OF MATERIALS, RUBBER BEEDING "I" ANGLE REQUIRED CHROMIUM PLATED SCREWS ETC., AND POWER CONSUMPTION CHARGES REQUIRED FOR FABRICATION INCLUDING MAKING NECESSARY HOLES IN THE COLUMNS, BEAMS, MASONRY WITH POWER DRILL TO THE REQUIRED EXTENT AND REDOING THE MASONRY TO ORIGINAL CONDITIONS AFTER FIXING ETC., COMPLETE. THE ALUMINIUM SECTION ANODIZED WITH MATT FINISH UNDER ELECTRICALLY CONTROLLED CONDITIONS IN ACCORDANCE WITH IS SPECIFICATION 1863/1963 FOR ANODIC FILM THICKNESS OF NOT 15 MICRONS ALL THE CLIPS. (THE QUALITY AND BRAND OF THE MATERIALS SHOULD BE GOT APPROVED BY THE EXECUTIVE ENGINEER BEFORE USE IN WORK)	Rs.3800.00 (Rupees three thousand and eight hundred only)	1.Sq.M. (ONE SQUARE METRE)	133000.00
9		SUPPLYING, FABRICATING AND FIXING IN POSITION OF ALUMINIUM ANODISED NATURAL COLOUR MATT FINISH OF SINGLE LEAF DOOR WITH 1/3 PANELLLED WITH 12MM THICK NOVAPAN SHEET AT BOTTOM AND 2/3 GLAZED USING 5.50MM THICK PLAIN GLASS AT TOP. THE OUTER FRAME TOP AND BOTTOM USING RECTANGULAR BOX SECTION NO.4617 OF 101.60X44.45X2.10MM AT WEIGHT OF 1.608 KG/MAND SHUTTER VERTICAL SECTION NO.4504 OF 47.62X47.62X1.82MM AT WEIGHT OF 1.052 AND TOP HORIZONTAL SECTION NO.4506 OF SIZE 47.62X10.16X2.82MM AT WEIGHT OF 0.776 KG/M WITH NECESSARY ACCESSORIES SUAH AS ALUMINIUM CLIPS, RUBBER BEADING, PVC FELT, ALUMINIUM HANDLE FOR A LENGTH OF SHUTTER (BOTH SIDES), LOCKING ARRANGEMENTS, FURNITURE FITTINGS SUCH AS 125MM ALUMINIUM HINGES-4 NOS. LOCK-1 NO. DOOR STOPPER WITH RUBBER BUSH AND REQUIRED CHROMIUM PLATED SCREWS ETC., INCLUDING COST OF MATERIALS LABOUR CHARGES AND POWER CONSUMPTION CHARGES			176097.45

For G.N.BUILDERS

CONTRACTOR

NO. OF CORRECTIONS

SUPERINTENDING ENGINEER/SOUTH CIRCLE.

S.NO 1	QUANTITY 2	DESCRIPTION OF WORK 3	RATE EXCLUSIVE OF GST IN FIGURES AND IN WORDS 4	UNIT IN FIGURES AND IN WORDS 5	AMOUNT 6
		REQUIRED FOR FABRICATION INCLUDING MAKING NECESSARY HOLES IN THE COLUMNS, BEAMS, MASONRY WITH POWER DRILL TO THE REQUIRED EXTENT AND REDOING THE MASONRY TO ORIGINAL CONDITIONS AFTER FIXING ETC., COMPLETE. THE ALUMINIUM SECTION ANODIZED WITH MATT FINISH UNDER ELECTRICALLY CONTROLLED CONDITIONS IN ACCORDANCE WITH IS SPECIFICATION 1863/1963 FOR ANODIC FILM THICKNESS OF NOT 15 MICRONS ALL THE CLIPS. (THE QUALITY AND BRAND OF THE MATERIALS SHOULD BE GOT APPROVED BY THE EXECUTIVE ENGINEER BEFORE USE IN WORK)			176097.45
	8.40 Sq.M.	SUITABLE DOOR OF SIZE a) 1000MM X 2100MM	Rs.7400.00 (Rupees seven thousand and four hundred only)	1.Sq.M. (ONE SQUARE METRE)	62160.00
10	14.60 Sq.M.	SUPPLYING AND FIXING UPVC (UN-PLASTICIZED POLYVINYL CHLORIDE) WINDOWS OF CASEMENT TYPE (OPEN) FROM THE PROFILE THE SIZE OF OUTER FRAME 60MM X 58MM AND SHUTTER PROFILE ARE REINFORCEMENT WITH GI/1MM 125GSM AND 100% CORROSION FREE, THE PROFILES ARE MULTI CHAMBERED SECTIONS WITH WALL THICK OF 2MM. THE EPDM RUBBER (BLACK COLOUR) COVERED WITH OVER ALL THE EDGES OF FRAME AND SHUTTER THE SHUTTER WILL BE PROVIDED WITH ESPAG MULTI POWER POINT LOCKS AND ALSO IT OPERATES AS HANDLE. THE CORNERS AND JOINTS SHOULD BE WELDED AND CLEANED. RADIATIONS FREE PIN HEADED PLAIN OR BROWN COLOUR GLASS 4MM THICK SHOULD BE PROVIDED TO THE SHUTTER AND IT SHOULD NOT ALLOW LEAKAGE OF WATER EVEN AT MOST RANGING STORMS AND SHOULD HAVE KEY LOCKABLE ACTION, SECURITY PROTECTIVE HINGES, STRONG LOCKING SYSTEMS AND AS PER SIZE FOR ARRESTING NOISE AND ENERGY LOSS. THE CONNECTING MECHANISM BETWEEN SASH AND OUTER FRAME THAT ENABLES OPENING OF THE WINDOW. THE WINDOW SHOULD BE FIXED TO THE WALL WITH 100% PACKING WITH SCREWS AND SILICON PACKING ALL ROUND THE FRAMES. THE WINDOW SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE ON WORK (THE QUALITY AND BRAND OF UPVC WINDOW SHOULD BE GOT APPROVED BY THE EXECUTIVE ENGINEER BEFORE USE)	Rs.7100.00 (Rupees seven thousand and one hundred only)	1.Sq.M. (ONE SQUARE METRE)	103660.00
11		SUPPLYING AND FIXING OF TEAK WOOD WROUGHT AND PUT UP FOR FRAMES OF DOORS, WINDOWS, VENTILATORS, CUPBOARD AND ANY OTHER SIMILAR JOINERY WORKS WITH NECESSARY PLUGS, REBATES FOR SHUTTERS, PLASTER GROOVES ON ALL FACES ETC., INCLUDING LABOUR CHARGES FOR FIXING HOLD FASTS. COMPLYING WITH RELEVANT STANDARD SPECIFICATIONS ETC.. IN ALL RESPECTS.			
	0.03 Cu.M.	(a) TEAK WOOD OVER 2.00 METRE AND BELOW 3.00 METRE LENGTH	Rs.124600.00 (Rupees one lakh twenty four thousand and six hundred only)	1.Cu.M. (ONE CUBIC METRE)	3738.00
	0.02 Cu.M.	(b) TEAK WOOD BELOW 2.00 METRE LENGTH	Rs.112400.00 (Rupees one lakh twelve thousand and four hundred only)	1.Cu.M. (ONE CUBIC METRE)	2248.00
					347903.45

For G.N.BUILDERS

CONTRACTOR

NO. OF CORRECTIONS

SUPERINTENDING ENGINEER/SOUTH CIRCLE.

S.NO	QUANTITY	DESCRIPTION OF WORK	RATE EXCLUSIVE OF GST IN FIGURES AND IN WORDS	UNIT IN FIGURES AND IN WORDS	AMOUNT
1	2	3	4	5	6
					347903.45
12	3.20 Sq.M.	SUPPLYING AND FIXING OF BEST INDIAN TEAK WOOD DOUBLE LEAF PANELLED DOOR SHUTTER IN POSITION USING 150MM X 37.5MM OUTER STYLES 6 NOS. 150MM X 37.5MM TOP & INTERMEDIATE RAILS AND 2 NOS 75MM X 37.5MM BOTTOM RAILS AND 18.75MM (AVERAGE) TK PLANKS FOR PANELS INCLUDING COST AND LABOUR FOR FIXING THE BRASS FITTINGS 4 NOS. OF 6" DOOR HANDLE, 8 NOS. OF 6" BUTT HINGES, 4 NOS. OF 10"x1/2" TOWER BOLT, 1 NO. OF MORTICE LOCK WITH HANDLE, 2 NOS. OF RUBBER BUSH - 40MM DIA AND 60MM LONG, 2 NOS. OF ALUMINIUM DOOR STOPPER WITH RUBBER BUSH WITH BRASS SCREWS BEST APPROVED QUALITY AND SHADE ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE BRASS FITTINGS SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USING).	Rs.6300.00 (Rupees six thousand and three hundred only)	1.Sq.M. (ONE SQUARE METRE)	20160.00
13	5 NOS.	SUPPLYING AND FIXING OF 20 AMPS DP PLUG AND SOCKET IN SHEET ENCLOSURE WITH 32A DP MCB IN FLUSH WITH WALL WITH EARTH CONNECTION (FOR AC PLUG) ETC ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE BRAND AND QUALITY OF THE MATERIAL SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE SUPPLY MADE).	Rs.1900.00 (Rupees one thousand and nine hundred only)	1.NO. (EACH)	9500.00
14	56.80 Sq.M.	PROVIDING AND FIXING IN POSITION OF 10MM THICK GYP BOARD FALSE CEILING USING GI PERIMETER CHANNEL OF SIZE 0.55MM THICK (HAVING ONE FLANGE OF 20MM THICK ANOTHER FLANGE OF 30MM AND WEB OF 27MM) ALONG WITH PERIMETER OF CEILING, SCREWS, FIXING BRICK WALL / PARTITION/RCC WORK WITH THE HELP OF NYLON SLEEVES AND SCREWS AT 610MM CENTRE TO CENTRE. THEN SUSPENDING GI INTERMEDIATE CHANNELS OF 45MM (0.90MM THICK WITH TWO FLANGES OF 15MM EACH) FROM THE SOFFITS AT 1220MM CENTRE TO CENTRE WITH CEILING ANGLE OF WIDTH 25X10X0.55MM THICK FIXED TO SOFFITS WITH GI CLEAT AND STEEL EXPANSION FASTENERS CEILING SECTION OF SIZE OF 0.55MM THICK HAVING KNURLD WEB OF 51.50MM AND TWO FLANGES OF 26MM EACH WITH LIPS OF 10.50MM ARE FIXED TO THE INTERMEDIATE CHANNEL WITH THE HELP OF CONNECTING CLIPS IN DIRECTION PERPENDICULAR TO THE INTERMEDIATE CHANNEL AT 457MM ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS.	Rs.900.00 (Rupees nine hundred only)	1.Sq.M. (ONE SQUARE METRE)	51120.00
15	12 NOS.	SUPPLYING AND FIXING OF 24W LED 4000K 1 X 1 SQUARE TYPE RECESSED FITTING WITH LED INCLUDING COST OF MATERIALS AND LABOUR CHARGES FOR FIXING IN POSITION ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE BRAND AND QUALITY OF THE MATERIALS SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	Rs.1800.00 (Rupees one thousand and eight hundred only)	1.NO. (EACH)	21600.00
16	2 NOS.	SUPPLYING AND FIXING OF 24W LED 4000K 2 X 2 SQUARE TYPE RECESSED FITTING WITH LED INDOOR FITTING INCLUDING COST OF MATERIALS AND LABOUR CHARGES FOR FIXING IN POSITION ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE BRAND AND QUALITY OF THE MATERIALS SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	Rs.3500.00 (Rupees three thousand and five hundred only)	1.NO. (EACH)	7000.00
					457283.45

For G.N.BUILDERS


 CONTRACTOR


 NO. OF CORRECTIONS


 SUPERINTENDING ENGINEER/SOUTH CIRCLE.

S.NO 1	QUANTITY 2	DESCRIPTION OF WORK 3	RATE EXCLUSIVE OF GST IN FIGURES AND IN WORDS 4	UNIT IN FIGURES AND IN WORDS 5	AMOUNT 6
					457283.45
17	12 POINTS	<p>WIRING WITH 1.5 SQMM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1 K.V. GRADE CABLE WITH CONTINUOUS EARTH BY MEANS OF 1.5 SQMM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1 K.V. GRADE CABLE IN FULLY CONCEALED PVC RIGID CONDUIT PIPE HEAVY DUTY WITH ISI MARK WITH SUITABLE SIZE MS BOX OF 16 G THICK CONCEALED AND COVERED WITH 3MM THICK LAMINATED HYLEM SHEET CONTROLLED BY 5 AMPS FLUSH TYPE SWITCH INCLUDING CIRCUIT MAINS COST OF ALL MATERIALS, SPECIALS ETC., ALL COMPLETE.</p> <p>(a) LIGHT POINT WITH CEILING ROSE</p>	<p>Rs.1500.00 (Rupees one thousand and five hundred only)</p>	<p>1 POINT (EACH POINT)</p>	18000.00
18	11 POINTS	<p>WIRING WITH 1.5 SQMM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1.K.V. GRADE CABLE WITH CONTINUOUS EARTH BY MEANS OF 1.5 SQMM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1.K.V. GRADE CABLE IN FULLY CONCEALED PVC RIGID CONDUIT PIPE HEAVY DUTY WITH ISI MARK WITH SUITABLE SIZE MS BOX OF 16G THICK CONCEALED AND COVERED WITH 3MM THICK LAMINATED HYLEM SHEET FOR FAN POINT CONTROLLED BY 5 AMPS FLUSH TYPE SWITCH INCLUDING CIRCUIT MAINS, COST OF ALL MATERIALS, SPECIALS, ETC., ALL COMPLETE.</p>	<p>Rs.1600.00 (Rupees one thousand and six hundred only)</p>	<p>1 POINT (EACH POINT)</p>	17600.00
19	11 NOS.	<p>SUPPLYING AND DELIVERY OF FOLLOWING ELECTRIC CEILING FAN WITH ISI MARK WITH BLADES AND DOUBLE BALL BEARING, CAPACITOR, ETC., COMPLETE WITH 300MM DOWN ROD, CANOPIES, CAPACITOR, SHACKLE BLADES WITH ELECTRONIC DIMMER SUITABLE FOR OPERATION ON 230 VOLTS 50 HTZ SINGLE PHASE AC SUPPLY CONFORMING TO ISS NO.374/79 AND PROVIDED WITH INSULATION. (THE BRAND SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE SUPPLY MADE).</p> <p>(a) 48" ELECTRIC FAN 1200MM SWEEP</p>	<p>Rs.1500.00 (Rupees one thousand and five hundred only)</p>	<p>1.NO. (EACH)</p>	16500.00
20	11 NOS.	<p>CHARGES FOR ASSEMBLING AND FIXING OF CEILING FAN OF DIFFERENT SWEEP WITH NECESSARY CONNECTIONS AND FIXING OF FAN REGULATOR ON THE EXISTING BOARD ETC., ALL COMPLETE (EXCLUDING COST OF FAN)</p>	<p>Rs.520.00 (Rupees five hundred and twenty only)</p>	<p>1.NO (EACH)</p>	5720.00
					515103.4

For G.N.BUILDERS

CONTRACTOR

NO. OF CORRECTIONS

SUPERINTENDING ENGINEER/SOUTH CIRCLE.

S NO	QUANTITY	DESCRIPTION OF WORK	RATE EXCLUSIVE OF GST IN FIGURES AND IN WORDS	UNIT IN FIGURES AND IN WORDS	AMOUNT
1	2	3	4	5	6
					515103.45
21	15 NOS.	SUPPLYING AND FIXING OF 4'18 WATTS CRYSTAL LED TUBE LIGHT AND FIXING THE TUBE LIGHT FITTINGS ON TEAK WOOD ROUND BLOCKS OF 75MM DIA OR 40MM DEEP SUSPENDED FROM CEILING OR MOUNTED ON THE WALL INCLUDING COST OF ALL MATERIALS AND LABOUR FOR FIXING IN POSITION ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE ENTIRE TUBE LIGHT FITTINGS SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	Rs.650.00 (Rupees six hundred and fifty only)	1.NO (EACH)	9750.00
22	5 POINTS	WIRING WITH 1.5 SQMM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1.K.V. GRADE CABLE WITH CONTINUOUS EARTH BY MEANS OF 1.5 SQMM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1.K.V. GRADE CABLE IN FULLY CONCEALED PVC RIGID CONDUIT PIPE HEAVY DUTY WITH ISI MARK WITH SUITABLE SIZE MS BOX OF 16G THICK CONCEALED AND COVERED WITH 3MM THICK LAMINATED HYLEM SHEET FOR 5 AMPS 5 PIN PLUG SOCKET POINT AT SWITCH BOARD ITSELF INCLUDING CIRCUIT MAINS, COST OF ALL MATERIALS, SPECIALS, ETC., ALL COMPLETE.	Rs.750.00 (Rupees seven hundred and fifty only)	1 POINT (EACH POINT)	3750.00
23	15 NOS.	SUPPLYING AND FIXING 15 AMPS 3 PIN PLUG TYPE SOCKET ON A SUITABLE MS BOX 16G THICK CONCEALED AND COVERED WITH 3 MM THICK LAMINATED HYLEM SHEET INCLUSIVE OF ALL CONNECTIONS AND COST OF ALL MATERIALS.	Rs.150.00 (Rupees one hundred and fifty only)	1 NO. (EACH)	2250.00
24	12 POINTS	WIRING WITH 1.5 SQMM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1.K.V. GRADE CABLE WITH CONTINUOUS EARTH BY MEANS OF 1.5 SQ.MM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1.K.V. GRADE CABLE IN FULLY CONCEALED PVC RIGID CONDUIT PIPE HEAVY DUTY WITH ISI MARK WITH SUITABLE SIZE MS BOX OF 1 NO (EACH) 16G THICK CONCEALED AND COVERED WITH 3MM THICK LAMINATED HYLEM SHEET FOR 5 AMPS 5 PIN PLUG SOCKET POINT AT CONVENIENT PLACES INCLUDING CIRCUIT MAINS, COST OF ALL MATERIALS, SPECIALS, ETC., ALL COMPLETE	Rs.1050.00 (Rupees one thousand and fifty only)	1 POINT (EACH POINT)	12600.00
25	1 NO.	SUPPLYING AND FIXING OF VERTICAL TPN DISTRIBUTION BOARDS (WITH MCCB INCOMER); DOUBLE DOOR; IP43, AS PER IS 8623 III; IMPACT RESISTANCE IK09; FRAME MCCB INCOMER & SINGLE PHASE/THREE PHASE MCBS AS OUTGOING (FOR POWER LOADS EXCEEDING 100A) 6 WAY, MCCB + 18 MODULES ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS.	Rs.10000.00 (Rupees ten thousand only)	1 NO. (EACH)	10000.00
					553453.4!

For G.N.BUILDERS

CONTRACTOR

NO. OF CORRECTIONS

SUPERINTENDING ENGINEER/SOUTH CIRCLE.

S.NO 1	QUANTITY 2	DESCRIPTION OF WORK 3	RATE EXCLUSIVE OF GST IN FIGURES AND IN WORDS 4	UNIT IN FIGURES AND IN WORDS 5	AMOUNT 6
					553453.45
26 +	20.00 Rmt. +	RUN OFF MAIN WITH 4 WIRES OF 10 SQMM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1 KV GRADE CABLE WITH CONTINUOUS EARTH BY MEANS OF 2.5 SQMM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1 KV GRADE CABLE IN FULLY CONCEALED 25MM DIA RIGID PVC CONDUIT PIPE WITH ISI MARK ETC. INCLUDING COST OF ALL MATERIALS, SPECIALS ETC. ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS.	Rs.550.00 (Rupees five hundred and fifty only)	1.Rmt. (ONE RUNNING METRE)	11000.00 +
27 +	54.00 Rmt. +	RUN OFF MAIN WITH 2 WIRES OF 2.5 SQMM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1 KV GRADE CABLE WITH CONTINUOUS EARTH BY MEANS OF 2.5 SQMM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1 KV GRADE CABLE IN FULLY CONCEALED 19/20MM DIA RIGID PVC CONDUIT PIPE WITH ISI MARK ETC. INCLUDING COST OF ALL MATERIALS, SPECIALS ETC. ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS.	Rs.200.00 (Rupees two hundred only)	1.Rmt. (ONE RUNNING METRE)	10800.00 +
28 +	30.00 Rmt. +	RUN OFF MAIN WITH 2 WIRES OF 1.5 SQ.MM. PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1 KV GRADE CABLE WITH CONTINUOUS EARTH BY MEANS OF 1.5 SQ.MM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1. K.V. GRADE CABLE IN FULLY CONCEALED 19MM/20MM DIA RIGID PVC CONDUIT PIPE HEAVY DUTY WITH ISI MARK COST OF ALL MATERIALS, SPECIALS ETC., ALL COMPLETE.	Rs.180.00 (Rupees one hundred and eighty only)	1.Rmt. (ONE RUNNING METRE)	5400.00 +
29 +	2 NOS. +	SUPPLYING AND FIXING OF 300 MM DIA SWEEP AC EXHAUST FAN OF APPROVED ISI QUALITY INCLUDING NECESSARY WALL OPENING, FIXING AND FINISHING THE WALL OPENING AND MAKING GOOD INCLUDING COST OF MATERIALS, LABOUR FOR FIXING, CHIPPING AND REDOING NECESSARY INTER CONNECTION, SCAFFOLDING, HIRE CHARGES FOR TOOLS AND PLANTS ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE QUALITY OF THE 300 MM DIA SWEEP AC EXHAUST FAN SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	Rs.2200.00 (Rupees two thousand and two hundred only)	1 NO. (EACH)	4400.00 +
30 +	1 NO. +	SUPPLYING AND FIXING OF PORCELIN WASH HAND BASIN (WHITE WITHOUT PEDESTAL), SUPERIOR VARIETY OF SIZE 550X400MM WITH ALL ACCESSORIES SUCH AS POWDER COATED CAST IRON BRACKETS, 32MM DIA C.P. WASTE COUPLING, RUBBER PLUG AND ALUMINIUM CHAIN, 32MM DIA 'B' CLASS G.I. PVC WASTE PIPE, ANGLE VALVE, 15MM DIA NYLON CONNECTION, 15MM DIA BRASS NIPPLES, 15MM C.P. PILLAR TAP & REQUIRED GRATING ETC., COMPLETE IN ALL RESPECTS (WASH HAND BASIN SHALL BE GOT APPROVED BY THE EXECUTIVE ENGINEER BEFORE FIXING).	Rs.3500.00 (Rupees three thousand and five hundred only)	1.NO. (EACH)	3500.00 +
					588553.45

For G.N.BUILDERS

CONTRACTOR

NO. OF CORRECTIONS

SUPERINTENDING ENGINEER/SOUTH CIRCLE.

S.NO 1	QUANTITY 2	DESCRIPTION OF WORK 3	RATE EXCLUSIVE OF GST IN FIGURES AND IN WORDS 4	UNIT IN FIGURES AND IN WORDS 5	AMOUNT 6
					588553.45
31	56.90 Sq.M.	SUPPLYING AND LAYING OF ANTI STATIC VINYL FLOORING (2MM THICKNESS) INCLUDING COST OF ADHESIVES, LABOUR CHARGES FOR CLEANING AND FIXING IN POSITION ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE QUALITY OF THE MATERIALS SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	Rs.950.00 (Rupees nine hundred and fifty only)	1.Sq.M. (ONE SQUARE METRE)	54055.00
32	8 NOS.	SUPPLYING AND DDELIVERY OF COMPUTER TABLE MADE OF 25MM THICK PARTICLE BOARD WITH MICCA FINISHING MOBILE BOX 17MM LAMINATION PARTICLE BOARD & CPU TRALLY KEY BOARD OF SIZE 60"X24"X30" & 18" INCLUDING COST OF ALL MATERIALS AND LABOUR CHARGES ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE QUALITY AND MODEL SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	Rs.18500.00 (Rupees eighteen thousand and five hundred only)	1.NO. (EACH)	148000.00
33	8 NOS.	SUPPLYING AND DELIVERY OF COMPUTER CHAIR INCLUDING COST OF ALL MATERIALS AND LABOUR CHARGES ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE QUALITY AND MODEL SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	Rs.5500.00 (Rupees five thousand and five hundred only)	1.NO. (EACH)	44000.00
34	8 NOS.	SUPPLYING OF STAINLESS STEEL (304 L GRADE) VISITOR CHAIR INCLUDING FABRIC CUSHIONED SEAT WITH PLAIN BLACK (MESH) & CHROME ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE QUALITY AND MODEL SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE.)	Rs.4900.00 (Rupees four thousand and nine hundred only)	1.NO. (EACH)	39200.00
35	1 NO.	SUPPLYING AND DELIVERY OF CONFERENCE TABLE MADE OF 25MM THICK PARTICLE BOARD WITH MICCA FINISHING OF SIZE (1200WX1200DX760H) INCLUDING COST OF MATERIALS AND LABOUR CHARGES FOR FIXING IN POSITION ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE QUALITY AND MODEL SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	Rs.8300.00 (Rupees eight thousand and three hundred only)	1.NO. (EACH)	8300.00
36	2 NOS.	SUPPLYING AND DELIVERY OF STAINLESS STEEL (304 L GRADE) 3 PERSON WAITING CHAIR INCLUDING COST OF MATERIALS AND LABOUR CHARGES FOR FIXING IN POSITION ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE QUALITY AND MODEL SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	Rs.10500.00 (Rupees ten thousand and five hundred only)	1.NO. (EACH)	21000.00
					903108.45

For G.N.BUILDERS

CONTRACTOR

NO. OF CORRECTIONS

SUPERINTENDING ENGINEER/SOUTH CIRCLE.

S.NO 1	QUANTITY 2	DESCRIPTION OF WORK 3	RATE EXCLUSIVE OF GST IN FIGURES AND IN WORDS 4	UNIT IN FIGURES AND IN WORDS 5	AMOUNT 6
					903108.45
37	1 NO.	SUPPLYING AND ERECTION OF 2 ZONE AUTOMATIC FIRE ALARM PANEL WITH FIRE AND FAULT INDICATIONS, LAMP TEST, ALARM CANCEL, SYSTEM RESET BUTTONS. PANEL SHALL HAVE GLASS FRONT DOOR, BATTERY BACK UP WITH INBUILT BATTERY CHARGER, PANEL SHALL OPERATE ON 230V AC SINGLE PHASE SUPPLY ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE QUALITY OF THE MATERIALS SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	Rs.17500.00 (Rupees seventeen thousand and five hundred only)	1.NO. (EACH)	17500.00
38	1 NO.	SUPPLYING AND INSTALLATION OF MANUAL CALL POINT WITH HAMMER . TO OPERATE ON 24V DC SUPPLY ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE BRAND AND QUALITY OF THE MATERIALS SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	Rs.1450.00 (Rupees one thousand four hundred and fifty only)	1.NO. (EACH)	1450.00
39	1 NO.	SUPPLYING AND INSTALLATION OF ELECTRONIC HOOTER 5 WATT CAPACITY WALL MOUNTING TYPE ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE BRAND AND QUALITY OF THE MATERIALS SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	Rs.1550.00 (Rupees one thousand five hundred and fifty only)	1.NO. (EACH)	1550.00
40	75.00 Rmt.	SUPPLYING AND INSTALLATION OF 2 CORE 1.5 SQMM COPPER LTUG CABLE RUN ON WALL, CEILING WITH CLAMPS, SCREW, JUNCTION BOXES ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE BRAND AND QUALITY OF THE MATERIALS, SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	Rs.110.00 (Rupees one hundred and ten only)	1.Rmt. (ONE RUNNING METRE)	8250.00
41	1 NO.	SUPPLYING AND INSTALLATION OF BIO-METRIC ATTENDANCE SYSTEM WITH DOOR LOCKING ARRANGEMENTS AND DOOR RELEASE BUTTONS INCLUDING CAT 5 CABLE LAYING UPTO THE COMPUTER TERMINAL AND ENTROLLMENT OF STAFF INCLUDING COST OF ALL MATERIALS AND LABOUR CHARGES ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE BRAND AND QUALITY OF THE MATERIALS SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	Rs.15000.00 (Rupees fifteen thousand only)	1.NO. (EACH)	15000.00
42	5 NOS.	SUPPLYING AND INSTALLATION OF PHOTO ELECTRIC SMOKE DETECTORS IN ELECTRICAL ROOM WITH BASE AND LED TO OPERATE ON 24V DE SUPPLY INCLUDING COST OF MATERIALS AND LABOUR CHARGES ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE BRAND AND QUALITY OF THE MATERIALS SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	Rs.2800.00 (Rupees two thousand and eight hundred only)	1.NO. (EACH)	14000.00
					960858.45

For G.N.BUILDERS

CONTRACTOR

NO. OF CORRECTIONS

SUPERINTENDING ENGINEER/SOUTH CIRCLE.

S.NO 1	QUANTITY 2	DESCRIPTION OF WORK 3	RATE EXCLUSIVE OF GST IN FIGURES AND IN WORDS 4	UNIT IN FIGURES AND IN WORDS 5	AMOUNT 6
					960858.45
43	1 NO.	SUPPLYING AND INSTALLATION OF CO2 TYPE FIRE EXTINGUISHERS WALL MOUNTING TYPE, CYLINDRICAL IN SHAPE, WITH INITIAL CHARGE, DISCHARGE HOSE, WALL BRACKETS CAPACITY 4.5 KGS ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE BRAND AND QUALITY OF THE MATERIALS SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	Rs.6900.00 (Rupees six thousand and nine hundred only)	1.NO. (EACH)	6900.00
44	3.00 Cu.M.	EARTH WORK EXCAVATION FOR OPEN FOUNDATION IN ALL SOILS AND SUB-SOILS TO THE REQUIRED DEPTH AS MAY BE DIRECTED EXCEPT IN HARD ROCK REQUIRING BLASTING, INCLUSIVE OF SHORING, STRUTTING AND BAILING OUT WATER WHEREVER NECESSARY (EXCLUDING REFILLING THE SIDES OF FOUNDATION) AND DEPOSITING THE EARTH IN PLACES SHOWN CLEARING AND LEVELLING THE SITE WITH AN INITIAL LEAD OF 10 METRES AND LIFT AS SPECIFIED HEREUNDER ETC., COMPLETE IN ALL RESPECTS COMPLYING WITH RELEVANT STANDARD SPECIFICATIONS. (EXCLUDING REFILLING)	Rs.120.00 (Rupees one hundred and twenty only)	1.Cu.M. (ONE CUBIC METRE)	360.00
45	3.00 Rmt.	SUPPLYING AND DELIVERY OF FOLLOWING DIA GI PIPE 'B' CLASS OF BEST APPROVED QUALITY CONFIRMING TO IS SPECIFICATIONS WITH ISI MARK FOR PROVIDING UG CABLE ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE QUALITY OF THE GI PIPES SHOULD BE GOT APPROVED FROM EXECUTIVE ENGINEER BEFORE USING).	Rs.200.00 (Rupees two hundred only)	1.Rmt. (ONE RUNNING METRE)	600.00
46	1 NO.	SUPPLYING AND FIXING OF COPPER PLATE OF SIZE 60CMX60CMX6MM THICK ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE QUALITY OF THE MATERIALS SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	Rs.20000.00 (Rupees twenty thousand only)	1.NO. (EACH)	20000.00
47	15.00 Rmt.	SUPPLYING AND FIXING OF COPPER PATTI 25MM WIDE AND 3MM THICK ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE QUALITY OF THE MATERIALS SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	Rs.1100.00 (Rupees one thousand and one hundred only)	1.Rmt. (ONE RUNNING METRE)	16500.00
48	7 NOS.	SUPPLYING AND FIXING OF BEST APPROVED SUPERIOR VARIETY CONCEALED TYPE FIBRE BOX WITH M.S. FAN HOOK OF 100MM DIA, 75MM DEPTH AND 3MM THICK INCLUDING COST AND FIXING IN POSITION ETC., COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE QUALITY SHOULD BE GOT APPROVED BY THE EXECUTIVE ENGINEER BEFORE USE)	Rs.34.00 (Rupees thirty four only)	1.NO. (EACH)	238.00
					1005456.45

For G.N.BUILDERS

CONTRACTOR

NO. OF CORRECTIONS

SUPERINTENDING ENGINEER/SOUTH CIRCLE.

S.NO 1	QUANTITY 2	DESCRIPTION OF WORK 3	RATE EXCLUSIVE OF GST IN FIGURES AND IN WORDS 4	UNIT IN FIGURES AND IN WORDS 5	AMOUNT 6
49	5 NOS.	SUPPLYING, INSTALLATION, TESTING AND COMMISSION OF 1.5 TON CAPACITY SPLIT TYPE AC UNIT WITH COPPER COIL 5 STAR RATED INVERTER SUPERIOR VARIETY/MAKE CONSISTING OF OUTDOOR CONDENSING UNIT COMPLETE WITH COMPRESSOR AND AIR COOLER CONDENSER WITH FAN MOTOR AND ONE INDOOR UNIT WITH EVAPORATOR BLOWER ETC., INCLUDING INITIAL CHARGING OF REFRIGERANT GAS AND SUITABLE FOR THREE PHASE OPERATION (WITH CARDLESS REMOTE CONTROL FACILITIES). ALL COMPLETE AND AS DIRECTED BY DEPARTMENTAL OFFICERS (THE QUALITY AND BRAND OF THE AC UNIT SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	Rs.46000.00 (Rupees forty six thousand only)	1 NO. (EACH)	1005456.45 230000.00
50	1 NO.	SUPPLYING AND FIXING OF 3 PHASE UPS (THREE PHASE IN & SINGLE PHASE OUT) SYSTEM WITH BATTERY 2 HOURS BACK UP 7.5 KVA CAPACITY ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE QUALITY AND BRAND OF UPS ARRANGEMENTS SHOULD BE GOT APPROVED BY THE EXECUTIVE ENGINEER BEFORE USE).	Rs.235000.00 (Rupees two lakhs and thirty five thousand only)	1.NO. (EACH)	235000.00
51	465.70 Sq.M.	FINISHING THE TOP OF ROOF WITH ONE COURSE OF HYDRAULIC PRESSED TILES OF APPROVED SUPERIOR QUALITY OF SIZE 23CMX23CMX20MM THICK LAID OVER WEATHERING COURSE IN CM 1:3 (ONE OF CEMENT AND THREE OF CRUSHED STONE SAND) 12MM THICK MIXED WITH WATER PROOFING COMPOUND AT 2% BY WEIGHT OF CEMENT USED AND POINTED NEATLY WITH THE SAME CEMENT MORTAR MIXED WITH WATER PROOFING COMPOUND INCLUDING CURING ETC., AS PER STANDARD SPECIFICATIONS. (THE QUALITY OF THE TILES SHALL BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE.)	Rs.1195.00 (Rupees one thousand one hundred and ninety five only)	1.Sq.M. (ONE SQUARE METRE)	556511.50
52	1 NO.	PROVIDING EARTHING STATION (TYPE I) USING PIPE ELECTRODE AS PER IS 3043 USING 2.5M OF 40MM DIA 1.0 M OF 20MM DIA B-CLASS GI PIPE AND 1.00M OF 15MM DIA B-CLASS GI PIPE INCLUDING EARTH WORK EXCAVATION, BRICK WORK IN CEMENT MORTAR AND PLASTERING AND COST OF FUNNEL, GI NUTS, BOLTS, WASHERS, CHECK NUTS, GI BEND, REDUCER AND COUPLING, C.I. COVER OF 30X30CM AND INCLUDING CHARCOAL OF 40 KGS AND SALT 10 KG ETC., ALL COMPLETE.	Rs.2900.00 (Rupees two thousand and nine hundred only)	1 NO. (EACH)	2900.00
53	56.80 Sq.M.	PAINTING THE NEW WALLS WITH TWO COATS OF APPROVED BEST READY MIXED PLASTIC EMULSION PAINT IN ADDITION TO ONE COAT OF APPROVED PRIMER COAT OVER CEMENT PLASTERED WALL SURFACES AND CEILING INCLUDING COST OF PLASTIC EMULSION PAINT, PUTTY, BRUSHES ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS (THE EMULSION PAINT AND ITS SHADE SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USING)	Rs.240.00 (Rupees two hundred and forty only)	1.Sq.M. (ONE SQUARE METRE)	13632.00
					2043499.95

For G.N.BUILDERS

CONTRACTOR

NO. OF CORRECTIONS

SUPERINTENDING ENGINEER/SOUTH CIRCLE.

S NO 1	QUANTITY 2	DESCRIPTION OF WORK 3	RATE EXCLUSIVE OF GST IN FIGURES AND IN WORDS 4	UNIT IN FIGURES AND IN WORDS 5	AMOUNT 6
					2043499.95
54 ✓	28.40 Cu.M. ✓	WEATHERING COURSE WITH CONCRETE BROKEN BRICK JELLY 20MM GAUGE IN PURE BURNT LIME STONE SLAKED AND SCREENED (NO SAND) OVER RCC ROOF SLAB WITH PROPORTION OF BRICK JELLY TO LIME (FAT LIME) BEING 32: 12 1/2 BY VOLUME WELL BEATEN WITH WOODEN BEATERS FOR GIVING THE REQUIRED SLOPE AND THICKNESS COMPLYING WITH RELEVANT STANDARD SPECIFICATION AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS.	Rs.3500.00 (Rupees three thousand and five hundred only) ✓	1.Cu.M. (ONE CUBIC METRE) ✓	99400.00 ✓
		TOTAL AMOUNT (EXCLUDING GST)			2142899.95
		GST Amount for providing Service to Government Contract Works for the above Construction Works.			257147.99
		GRAND TOTAL			2400047.94
(RUPEES TWENTY FOUR LAKHS AND FORTY SEVEN AND PAISE NINETY FOUR ONLY)					

for G.N.BUILDERS



CONTRACTOR



NO. OF CORRECTIONS



SUPERINTENDING ENGINEER/SOUTH CIRCLE.