

SE/South Circle. Agt. No. 84/2022-2023

FILE No. DB/SC/3525/2022

REPORT ACCOMPANYING SLIP FOR LUMP SUM AGREEMENT
(FOR OFFICE USE ONLY)

TAMILNADU POLICE HOUSING CORPORATION LTD.,
SOUTH CIRCLE, MADURAI – 625 014.

NAME OF PROJECT : Police Buildings – Special Repair works
-2022 -2023 ✓

NAME OF WORK : Special repair works for the existing 1 No. of
INS, 2 Nos. of SI and 40 Nos. of PC/HC
quarters at Nanguneri in Tirunelveli District
for the year 2022-2023. ✓

ESTIMATE AMOUNT : ₹ 61,05,100/- ✓

ESTIMATE No. : CER No.52/2022-2023 ✓

ESTIMATE AMOUNT PUT IN TENDER : ₹ 59,02,364.37 (2022-2023) ✓
(Including the GST @12%)

TENDER VALUE : ₹ 46,49,982.95 (Including the GST @12%) ✓

LESS AMOUNT : (-) ₹ 12,52,381.42 ✓

LESS PERCENTAGE : (-) 21.22 % ✓

TENDER ACCEPTED BY WHOM : The Chairman and Managing Director,
TNPHC Ltd., Chennai-10 ✓

NAME OF THE CONTRACTOR : Thiru. A. VENKATESAN ✓

No. OF ITEMS IN THE AGREEMENT : 58 (Fifty eight only) ✓

No. OF PAGES IN THE AGREEMENT : 68 (Sixty eight only) ✓

No. OF CORRECTIONS IN THE }
AGREEMENT : Nil ✓

Dr. S. S. Srinivasan 7/11/22
SUPERINTENDING ENGINEER
SOUTH CIRCLE, TNPHC LTD.,



தமிழ்நாடு தமிழ்நாடு TAMILNADU
03 NOV 2022

A. வெங்கடேசன்
திருநெல்வேலி

CG 985805
T. Moenashil Bar
T. சீனாச்சுபாபா
முத்திரைத்தாள் விற்பனை
19/3, கரண் சென்ட்ரி
கோகலே ரோடு, மதுரை
RC. No. 1761 / B1 / 2787
TAMIL NADU POLICE HOUSING CORPORATION LIMITED,
SOUTH CIRCLE, MADURAI - 625 014.

ARTICLES OF AGREEMENT


ARTICLES OF AGREEMENT made this Seventh day of November 2022
BETWEEN the Tamil Nadu Police Housing Corporation Limited, (hereinafter called the Corporation
Limited which expression shall where the context so admits include its successors in office and assigns) of
the ONE PART and

Thiru. A. VENKATESAN,
NO.1, NAINARKULAM STREET,
NORTH CAR STREET,
TIRUNELVELI - 627 006.

(Hereinafter called the contractor which expression shall where the context so admits include its heirs,
executors, administrators and legal representatives) of the OTHER PART


Contractor


No. of corrections


Superintending Engineer/ South Circle

3

A

TAMIL NADU POLICE HOUSING CORPORATION LIMITED.,
SOUTH CIRCLE, MADURAI – 625 014.

ARTICLES OF AGREEMENT

ARTICLES OF AGREEMENT made this _____ day of _____
BETWEEN the Tamil Nadu Police Housing Corporation Limited, (hereinafter called the Corporation Limited which expression shall where the context so admits include its successors in office and assigns) of the ONE PART and


Thiru. A. VENKATESAN,
NO.1, NAINARKULAM STREET,
NORTH CAR STREET,
TIRUNELVELI - 627 006.

(Hereinafter called the contractor which expression shall where the context so admits include its heirs, executors, administrators and legal representatives) of the OTHER PART

WHEREAS the corporation Limited is desirous of **Special repair works for the existing 1 No. of INS, 2 Nos. of SI and 40 Nos. of PC/HC quarters at Nanguneri in Tirunelveli District for the year 2022-2023** and have caused an estimate of probable quantities contained in schedule A, drawings and specifications describing the work to be done to be prepared.

AND WHEREAS the said schedule A, drawings (schedule B) and the specifications (schedule C) and other schedules herewith annexed have been signed by or on behalf of the parties hereto.

AND WHEREAS the contractor has agreed to the retention, by the Corporation Limited of earnest money (with GST) of ₹ **44,600/- (Rupees forty four thousand and six hundred only)** in the form of NSC Scheme Savings Bank Pass Book A/c No: 4055301433 Dated: 01.06.2018 Issued by Post Office Tirunelveli H.O, Department of Posts, India paid by him when he submitted his tender, as security for the due fulfillment of the contract to the satisfaction of the Corporation Limited or any other officer authorized by the Corporation Limited.


Contractor


No. of corrections


Superintending Engineer/South Circle.

5

AND WHEREAS the Contractor has ~~been~~ [✓] a further sum of ₹ 4,75,900/- (**Rupees four lakhs seventy five thousand and nine hundred only**) paid in the form of **National (Small) Savings Scheme Pass Book Issued by Post Office Tirunelveli H.O, Department of Posts, India and the details are as follows**

1. A/c No. 4055318073 Dated: 01.06.2018	: ₹ 55,800.00
2. A/c No. 4251875240 Dated: 09.01.2019	: ₹ 46,600.00
3. A/c No. 020001259483 Dated: 18.01.2021	: ₹ 59,000.00
4. A/c No. 020053856580 Dated: 29.10.2022	: ₹ 3,14,500.00
	=====
Total	: ₹ 4,75,900.00
	=====


against the balance of the security deposit and additional security deposit amount of ₹ 4,75,700/- (with GST) for the due fulfillment of the contract to the satisfaction of the Corporation Limited or any other officer authorized by the Corporation Limited

AND WHEREAS the Contractor has also signed a copy of the Tamilnadu Building practice and the addenda volume there to maintained in the office of the Superintending Engineer /South Circle Tamil Nadu Police Housing Corporation Limited in acknowledgement of being bound by all the conditions of the clauses of the general conditions of contract and all the standard specifications for items of works described by a standard Specification number in Schedule – A.

AND WHEREAS the contractor has agreed to execute upon and subject to the conditions set forth in the conditions of contract of the Tamil Nadu Building Practice and such other conditions as are contained in all the specifications forming part of this contract (hereinafter referred to as “the said conditions”) the work shown upon the drawings and described in the said specifications and set forth in Schedule –A as the “Probable Quantities” and comply with the rate of progress noted at the end of this ARTICLES OF AGREEMENT, for a sum of ₹ 46,49,982.95 (**Rupees forty six lakhs forty nine thousand nine hundred and eighty two and paise ninety five only**) or such other sum as may be arrived at under the clause of the General conditions of contract relating to “Payment on lumpsum basis or by final measurement at Unit Prices”

Now it is hereby agreed as follows:

1. In consideration of the payment of the said sum of ₹ 46,49,982.95 (**Rupees forty six lakhs forty nine thousand nine hundred and eighty two and paise ninety five only**) or such other sum as may be arrived at under the clause of the General conditions of contract relating


Contractor


No. of corrections


Superintending Engineer/South Circle.

A-7

to Payment on lumpsum basis or by final measurement at unit prices, the contractor will upon and subject to the said conditions execute and complete the works shown upon the said drawings and described in the said specifications and to the extent of the probable quantities shown in schedule A, with such variations by way of alterations of, additions to, or deductions from, the said works and method of payment there for are as provided for in the said conditions.


2. The term "Corporation Limited" in the said conditions shall mean the Tamil Nadu Police Housing Corporation Limited or any officer of the Corporation Limited incharge of the works who shall be competent to exercise all the powers and privileges reserved herein, in favour of the Corporation Limited with the previous sanction of the Corporation Limited or any other officer authorized by the Corporation Limited.
3. The arbitrator for fulfilling the duties set forth in the arbitration clause of the General conditions of contract shall be the Chief Engineer, Tamil Nadu Police Housing Corporation Limited upto value of claims of Rs. 50,000/- If the value of claims exceeds Rs. 50,000/- the matter shall be referred to the court having jurisdiction over Tamil Nadu state.
4. Time shall be considered as the essence of the agreement and the Contractor hereby agrees to commence the work as soon as this agreement is accepted by the Corporation Limited or any other officer authorized by the Corporation Limited and the site (or premises) is handed over to them as provided for in the said conditions and agrees to complete the work within **SIX** months from the date of such handing over the site (or premises) and to show progress as defined in the tabular statement "RATE OF PROGRESS" below, subject nevertheless to the provisions for extension of time contained in clause 56 of the General conditions of contract.

Rate of Progress

The following rate of progress and proportionate value of work done from time to time, as will be indicated by the Executive Engineer's Certificate of the value of work done will be required.

Date of commencement of this programme will be the date on which the site (or premises) is handed over to the Contractor.

Period after date of Commencement (1)	Percentage of work completed (Based on Contract lumpsum amount) (2)
I – Month	15 %
II – Month	30 %
III – Month	45 %
IV – Month	60 %


Contractor


No. of corrections


Superintending Engineer/South Circle .

De 9

V - Month

80 %

VI - Month

100 %

5. "The said conditions " shall be read and construed as forming part of this agreement and the parties hereto will respectively abide by and submit themselves to the conditions and stipulations and perform the agreements on their parts, respectively.
6. Upon the terms and conditions of this agreement being fulfilled and performed to the satisfaction of the Corporation Limited or any other officer authorized by the Corporation Limited, the security deposited by the contractor as herein before recited or such portion thereof as they may be entitled to under the said conditions shall be returned to the contractor.

IN WITNESS WHERE OF the contractor **Thiru. A. VENKATESAN** has hereunto set his hand and the Superintending Engineer/South Circle of Tamil Nadu Police Housing Corporation Limited on behalf of the Corporation Limited have hereunto set his hand, the day and year first above written.

Signed by the Contractor



Address


Thiru. A. VENKATESAN,
NO.1, NAINARKULAM STREET,
NORTH CAR STREET,
TIRUNELVELI - 627 006.



Contractor



No. of corrections



Superintending Engineer/South Circle.

TAMIL NADU POLICE HOUSING CORPORATION LIMITED

No.1, INSPECTOR QUARTERS, TSP 6 TH BATTALION CAMPUS,
NEW NATHAM ROAD, MADURAI – 625014.

Schedule 'A'

- A. The quantities given here are those upon which the lumpsum tender cost of the work is based, but they are subject to alterations, omissions, deductions or additions are provided for in the conditions of this contract and do not necessarily show the actual quantities of work to be done. The unit rates excluding GST amount quoted are those governing payments for extras or deductions or omissions according to the conditions of the contract set forth in the general conditions of the contract of the Tamil Nadu Building practice and other conditions or specifications of this contract.
- B. It is to be expressly understood that the measured work is to be taken net (notwithstanding any custom of practice to the contrary) according to the actual quantities when in place and finished according to the drawing or as may be ordered from time to time by the Chief Engineer and the cost calculated by measurement or Weight at the respective prices without any additional charges for any necessary or contingent works connected herewith. The rates quoted excluding GST amount are for works in situ and complete in every respect.
- C. Unavoidable delays may entail in rare instances, for delays beyond 3 months after execution of agreement, offer may be withdrawn/cancelled, validity shall be however optional subject to mutual consent by the contractor and TNPHC at agreed rates without extras.
- D. As a result of continuous improvements contemplated by the TNPHC in layouts/type design, substantial variations might occur in one more items. The tenderer will be expected to adopt such modifications whenever necessitated and ordered for.
- E. If rarely owing to non availability of vacant lands in the site mentioned in the notification change of site either partly or wholly is warranted, the tenderer shall accept to execute work accordingly as may be necessitated and ordered for at agreed rates or derived rates.


CONTRACTOR


NO. OF CORRECTIONS


SUPERINTENDING ENGINEER/SOUTH CIRCLE

SCHEDULE - A

NAME OF WORK : SPECIAL REPAIR WORKS FOR THE EXISTING 1 NO. OF INS, 2 NOS. OF SI AND 40 NOS. OF PC/HC QUARTERS
AT NANGUNERI IN TIRUNELVELI DISTRICT FOR THE YEAR 2022-2023

ITEM NO	QUANTITY	DESCRIPTION OF WORK	TNBP No.	RATE EXCLUSIVE FOR GST IN FIGURES AND IN WORDS	REBATE @ 16.60%	
					UNIT IN FIGURES AND IN WORDS	AMOUNT
1	2	3	4	5	6	7
37.1	855.60 Sq.M.	WHITE WASHING THREE COATS USING CLEAN SHELL LIME SLAKED INCLUDING COST OF LIME, GUM, BLUE, BRUSHES, INCLUDING SCAFFOLDING ETC., COMPLETE IN ALL RESPECTS	✓ 63	Rs.39.00 (Rupees thirty nine only)	1.Sq.M. (ONE SQUARE METRE)	33368.40
39	1058.40 KG.	SUPPLYING AND FIXING MILD STEEL GRILLS AS PER THE DESIGN APPROVED TO VERANDAH ENCLOSURE OR GATE INCLUDING ONE COAT OF PRIMER AND LABOUR FOR FIXING IN POSITION ETC. ALL COMPLETE.	✓	Rs.100.00 (Rupees one hundred only)	1.KG. (ONE KILOGRAM)	105840.00
41	13.25 Sq.M.	PAINTING THE NEW IRON WORK AND OTHER SIMILAR WORKS SUCH AS PVC / ASTM PIPES, KERB STONE AND GRILLS WITH TWO COATS OF APPROVED FIRST CLASS SYNTHETIC ENAMEL READY MIXED PAINT OF APPROVED QUALITY AND BRAND, THE PAINT SHOULD BE SUPPLIED BY THE CONTRACTOR AT HIS OWN COST, (THE QUALITY AND THE BRAND OF PAINT SHOULD BE GOT APPROVED BY THE EXECUTIVE ENGINEER BEFORE USE) COMPLYING WITH RELEVANT STANDARD SPECIFICATIONS.	✓ 66 & 66A	Rs.140.00 (Rupees one hundred and forty only)	1.Sq.M. (ONE SQUARE METRE)	1855.00
52		SUPPLYING, LAYING, FIXING AND JOINTING THE FOLLOWING PVC PIPES AS PER ASTM D - 1785 OF SCHEDULE 40 OF WALL THICKNESS NOT LESS THAN THE SPECIFIED IN IS 4985 SUITABLE FOR PLUMBING BY THREADING OF WALL THICKNESS INCLUDING THE COST OF SUITABLE PVC/GI SPECIALS /GM SPECIALS LIKE ELBOW, TEE REDUCERS, PLUG, UNION, BEND, COUPLER, NIPPLE/ GM GATE VALVE, CHECK AND WHEEL VALVE ETC., WHEREVER REQUIRED ABOVE THE GROUND LEVEL INCLUDING THE COST OF TEFLON TAPE, SPECIAL CLAMPS, NAILS, ETC., FIXING ON WALL TO THE PROPER GRADIENT AND ALIGNMENT AND REDOING THE CHIPPED OF MASONRY ETC., AS DIRECTED BY THE DEPARTMENTAL OFFICERS.				
	240.00 Rmt.	a) 32MM ASTM D SCHEDULE 40 THREADED PVC PIPE WITH NECESSARY PVC/GI SPECIALS	✓	Rs.225.00 (Rupees two hundred and twenty five only)	1.Rmt. (ONE RUNNING METRE)	54000.00
	286.00 Rmt.	b) 25MM ASTM D SCHEDULE 40 THREADED PVC PIPE WITH NECESSARY PVC/GI SPECIALS	✓	Rs.208.00 (Rupees two hundred and eight only)	1.Rmt. (ONE RUNNING METRE)	59488.00
	30.00 Rmt.	c) 20MM ASTM D SCHEDULE 40 THREADED PVC PIPE WITH NECESSARY PVC/GI SPECIALS	✓	Rs.203.00 (Rupees two hundred and three only)	1.Rmt. (ONE RUNNING METRE)	6090.00
74	46 NOS.	ELECTRICAL ARRANGEMENTS CHARGES FOR ASSEMBLING AND FIXING OF CEILING FAN OF DIFFERENT SWEEP WITH NECESSARY CONNECTIONS AND FIXING OF FAN REGULATOR ON THE EXISTING BOARD ETC., ALL COMPLETE (EXCLUDING COST OF FAN)	✓	Rs.520.00 (Rupees five hundred and twenty only)	1.NO (EACH)	23920.00
						284561.40

CONTRACTOR

NO. OF CORRECTIONS

SUPERINTENDING ENGINEER/SOUTH CIRCLE.

2015

ITEM NO	QUANTITY	DESCRIPTION OF WORK	TNBP No.	RATE EXCLUSIVE FOR GST IN FIGURES AND IN WORDS	REBATE @ 1% 3%	
					UNIT IN FIGURES AND IN WORDS	AMOUNT
1	2	3	4	5	6	7
						284561.40
8.4.1		<p>ANNEXURE</p> <p>PROVIDING AND LAYING IN POSITION, STANDARDISED CONCRETE MIX M-20 GRADE IN ACCORDANCE WITH IS: 456 - 2000 USING 20 MM AND DOWNGRADED HARD BROKEN STONE JELLY FOR ALL RCC ITEMS OF WORKS NAMELY TEE, ELL OR RECTANGULAR BEAMS, LINTELS, PARAPET CUM DROPS, WAIST AND LANDING SLAB, CANOPHY, CIRCULAR COLUMN, FIN PROJECTIONS, SUNSHADES, WINDOW BOXING SLAB, SLAB AND OTHER SIMILAR WORKS WITH MINIMUM CEMENT CONTENT OF 325 KG/M3 AND MAXIMUM WATER CEMENT RATIO OF 0.55, INCLUDING ADMIXTURE (PLASTICISER/SUPER PLASTICISER) IN RECOMMENDED PROPORTIONS</p> <p>AS PER IS:9103 TO ACCELERATE, RETARD SETTING OF CONCRETE, IMPROVE WORKABILITY WITHOUT IMPAIRING STRENGTH AND DURABILITY WITH ABOUT (5.0 CU.M) 7730 KG. OF 20 MM MACHINE CRUSHED STONE JELLY AND WITH ABOUT (3.3 CU.M.) 5156 KG. OF 10 -12 MM MACHINE CRUSHED STONE JELLY AND WITH ABOUT (4.79 CU.M) 7670 KG. OF CRUSHED STONE SAND FOR MAKING 10M3 CONCRETE BUT EXCLUDING COST OF REINFORCEMENT GRILL AND FABRICATING CHARGES, CENTERING AND SHUTTERING AND ALSO INCLUDING LAYING, VIBRATING WITH MECHANICAL VIBRATORS, FINISHING, CURING ETC., AND PROVIDING FIXTURES LIKE FAN CLAMPS IN THE RCC FLOOR/ROOF SLABS WHEREVER NECESSARY WITHOUT CLAIMING EXTRA, ETC., COMPLETE COMPLYING WITH STANDARD SPECIFICATION AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. THE COARSE AND FINE AGGREGATES TO BE USED SHOULD COMPLY WITH THE REQUIREMENTS OF IS STANDARDS. (NO SEPARATE PAYMENT WILL BE MADE BY THE DEPARTMENT FOR THE EXCESS USAGE OF MATERIALS).</p>				
	0.65 Cu.M.	(a) IN GROUND FLOOR		Rs.7300.00 (Rupees seven thousand and three hundred only)	1.Cu.M. (ONE CUBIC METRE)	4745.00
	0.55 Cu.M.	(b) IN FIRST FLOOR		Rs.7500.00 (Rupees seven thousand and five hundred only)	1.Cu.M. (ONE CUBIC METRE)	4125.00
	0.55 Cu.M.	(c) IN SECOND FLOOR		Rs.7700.00 (Rupees seven thousand and seven hundred only)	1.Cu.M. (ONE CUBIC METRE)	4235.00
16.1.1		<p>PRECAST CEMENT CONCRETE JALLY VENTILATOR IN STANDARDISED CONCRETE MIX M-20 GRADE IN ACCORDANCE WITH IS: 456 - 2000 USING 20MM AND DOWNGRADED HARD BROKEN STONE JELLY FOR THE ABOVE RCC ITEM OF WORK WITHOUT VIBRATING CHARGES EXCLUDING THE COST AND FABRICATION OF REINFORCEMENT GRILLS BUT INCLUDING PRECASTING, MOULDING, CURING, FINISHING AND FIXING IN POSITION COMPLYING WITH RELEVANT STANDARD SPECIFICATIONS ETC., COMPLETE IN THE FOLLOWING FLOORS.</p> <p>50 MM THICK</p>				
	7.60 Sq.M.	(a) IN GROUND FLOOR		Rs.2560.00 (Rupees two thousand five hundred and sixty only)	1.Sq.M. (ONE SQUARE METRE)	19456.00
	7.60 Sq.M.	(b) IN FIRST FLOOR		Rs.2600.00 (Rupees two thousand and six hundred only)	1.Sq.M. (ONE SQUARE METRE)	19760.00
						336882.40

CONTRACTOR

NO. OF CORRECTIONS

SUPERINTENDING ENGINEER/SOUTH CIRCLE

ITEM No.	QUANTITY	DESCRIPTION OF WORK	TNBP No.	RATE EXCLUSIVE FOR GST IN FIGURES AND IN WORDS	REBATE @ 16.60%	
					UNIT IN FIGURES AND IN WORDS	AMOUNT
						336882.40
18.1	✓ 10.30 Sq.M.	(c) IN SECOND FLOOR	✓	Rs.2700.00 (Rupees two thousand and seven hundred only)	1.Sq.M. (ONE SQUARE METRE)	27810.00
	✓ 47.60 Sq.M.	(b) PLAIN SURFACES SUCH AS ROOF SLAB, FLOOR SLAB, BEAMS LINTELS, LOFTS, SILL SLAB, STAIRCASE WAIST, PORTICO SLAB AND OTHER SIMILAR WORKS	✓	Rs.800.00 (Rupees eight hundred only)	1.Sq.M. (ONE SQUARE METRE)	38080.00
	✓ 30.55 Sq.M.	(c) FOR SQUARE AND RECTANGULAR COLUMNS, AND SMALL QUANTITIES SUCH AS SUNSHADE, PARAPET CUM DROPS, WINDOW BOXING, FIN PROJECTION AND OTHER SIMILAR WORKS	✓	Rs.1000.00 (Rupees one thousand only)	1.Sq.M. (ONE SQUARE METRE)	30550.00
21.5.2	11.05 Sq.M.	PROVIDING AND FIXING OF FACTORY MADE UNPLASTICIZED POLYVINYL CHLORIDE (UPVC) DOOR FRAME OF SIZE 50X47MM WITH A WALL THICKNESS OF 5MM, MADE OUT OF EXTRUDED 5MM RIGID UPVC FOAM SHEET, MITERED AT TWO CORNERS AND JOINED WITH 2 NOS. OF 150MM LONG BRACKETS OF 15X15MM M.S SQUARE TUBE. THE TWO VERTICAL AND HORIZONTAL DOOR PROFILES ARE TO BE REINFORCED WITH 19X19MM M.S SQUARE TUBE OF 19 GAUGES WITH PRIMER COAT. THE DOOR FRAME SHALL BE FIXED TO THE WALL USING 65MM/100MM LONG M.S SCREW THROUGH THE FRAME BY USING PVC FASTENERS. A MINIMUM OF 4 NOS. SCREWS TO BE PROVIDED FOR EACH VERTICAL MEMBER AND MINIMUM 2 NOS. FOR HORIZONTAL MEMBER ETC., PROVIDING AND FIXING OF 30MM THICK FACTORY MADE DOOR SHUTTER WITH UNPLASTICIZED POLYVINYL CHLORIDE (UPVC) SOLID PANEL FOAM SHEET, STRUCTURED WITH M.S.TUBE OF 19 GAUGE THICKNESS AND SIZE 19MM X 19MM FOR STYLES AND 15MM X 15MM FOR TOP RAIL AND BOTTOM RAIL. PANNELLING OF 5MM THICK UPVC ONE SIDE PRINTED LAMINATION SINGLE SHEET TO BE FITTED IN THE M.S.FRAME WELDED / SEALED TO THE STYLES AND RAILS COVERED WITH 5MM THICK HEAT MOULDED UPVC 'C' CHANNEL OF 30MMX50MM AND 5MM THICK 75MM WIDE UPVC SHEET FOR TOP RAIL, LOCK RAIL AND BOTTOM RAIL ON EITHER SIDE AND 10MM (5MM X 2 NOS.) THICK, 20MM WIDE CROSS UPVC SHEET AS GAP INSERT FOR TOP RAIL AND BOTTOM RAIL, AND JOINED TOGETHER WITH PVC SOLVENT CEMENT ADHESIVE. AN ADDITIONAL 5MM THICK UPVC STRIP OF 20MM WIDTH IS TO BE STUCK ON THE INTERIOR SIDE OF THE 'C' CHANNEL USING PVC SOLVENT CEMENT ADHESIVE. THE COST AND LABOUR CHARGES FOR FIXING OF 3 NOS. 4" SS BUTT HINGES AND ALUMINIUM FURNITURE FITTING SUCH AS 1 NO. 4" TOWER BOLT, 1 NO.5" ALDROP, 2 NOS. 6" FLAT 'D' TYPE HANDLE, ETC ARE INCLUDED. THE FITTING PROVIDED SHALL BEAR ISI MARKS. TO ENSURE THE GENUINITY OF PRODUCT, THE	✓	Rs.3200.00 (Rupees three thousand and two hundred only)	1.Sq.M. (ONE SQUARE METRE)	35360.00
						468682.40

CONTRACTOR

NO. OF CORRECTIONS

SUPERINTENDING ENGINEER/SOUTH CIRCLE.

ITEM	QUANTITY	DESCRIPTION OF WORK	TNBP No.	RATE EXCLUSIVE FOR GST IN FIGURES AND IN WORDS	REBATE @ 16%	
					UNIT IN FIGURES AND IN WORDS	AMOUNT
1	2	3	4	5	6	7
		DOOR SET SHOULD HAVE 4 NUMBERS OF MANUFACTURER'S LOGO HOLOGRAM OF APPROVED BRAND, EACH AT FRAME, STYLE, RAIL AND INNER PANEL. (THE QUALITY AND BRAND OF DOOR SHUTTER AND FURNITURE FITTINGS SHOULD BE GOT APPROVED BY THE EXECUTIVE ENGINEER BEFORE USE)				468682.40
23.2.1	70.00 Sq.M.	SUPPLYING AND FIXING OF 4 MM THICK PIN HEADED GLASS PANELS WITH ALUMINIUM ANODIZED 'U' SHAPE BEADING OF SIZE 12X12 MM WITH 107 GRAM IN AVERAGE WEIGHT FOR 1 M LENGTH WITH ALUMINIUM BOLTS AND NUTS FOR THE SHUTTERS OF THE STEEL WINDOWS ALREADY SUPPLIED TO SUIT ALL THE SIZE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE QUALITY OF GLASS AND ALUMINIUM BEEDING SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	✓	Rs.700.00 (Rupees seven hundred only)	1.Sq.M. (ONE SQUARE METRE)	49000.00
29.9.1	9.75 Sq.M.	SUPPLYING AND LAYING OF CERAMIC TILES (ANTI SKID) OF BEST APPROVED QUALITY FOR FLOORING AND OTHER SIMILAR WORKS (THE COLOUR AND SHADE SHALL BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USING) OVER CEMENT MORTOR 1:3 (ONE OF CEMENT AND THREE OF CRUSHED STONE SAND) 20MM THICK INCLUDING FIXING IN POSITION, CUTTING THE TILES TO THE REQUIRED SIZE WHEREVER NECESSARY, POINTING THE JOINTS WITH GROUT (TILE JOINT FILLER), CURING, FINISHING ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE BRAND AND QUALITY OF TILES SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE).	✓	Rs.1100.00 (Rupees one thousand and one hundred only)	1.Sq.M. (ONE SQUARE METRE)	10725.00
29.9.3	1144.95 Sq.M.	REPOLISHING THE MOSAIC FLOORING INCLUDING REQUIRED POLISHING STONES, COST OF ALL POLISHING MATERIALS AND HIRE CHARGES FOR POLISHING MACHINE ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS.	✓	Rs.60.00 (Rupees sixty only)	1.Sq.M. (ONE SQUARE METRE)	68697.00
32.1.1	559.95 Sq.M.	FINISHING TOP OF ROOF WITH ONE COURSE OF HYDRAULIC PRESSED TILES OF APPROVED SUPERIOR QUALITY OF SIZE 23CMX 23CMX20MM THICK LAID OVER WEATHERING COURSE IN CM 1:3 (ONE OF CEMENT AND THREE OF CRUSHED STONE SAND) 12MM THICK MIXED WITH WATER PROOFING COMPOUND AT 2% BY WEIGHT OF CEMENT USED AND POINTED NEATLY WITH THE SAME CEMENT MORTAR MIXED WITH WATER PROOFING COMPOUND INCLUDING CURING ETC., AS PER STANDARD SPECIFICATIONS. (THE QUALITY OF TILES SHALL BE GOT APPROVED FROM THE EE BEFORE USE)	✓	Rs.1075.00 (Rupees one thousand and seventy five only)	1.Sq.M. (ONE SQUARE METRE)	601946.25
33.1	614.60 Sq.M.	PLASTERING WITH CM 1:5 (ONE OF CEMENT AND FIVE OF CRUSHED STONE SAND) 12MM THICK FINISHED WITH NEAT CEMENT INCLUDING PROVIDING BAND CORNICE, CEILING CORNICE, CURING, SCAFFOLDING ETC., COMPLETE IN ALL RESPECTS AND COMPLYING WITH RELEVANT STANDARD SPECIFICATIONS.	✓	Rs.220.00 (Rupees two hundred and twenty only)	1.Sq.M. (ONE SQUARE METRE)	135212.00
						1334262.65



CONTRACTOR



NO. OF CORRECTIONS



SUPERINTENDING ENGINEER/SOUTH CIRCLE

ITEM	QUANTITY	DESCRIPTION OF WORK	TNBP No.	RATE EXCLUSIVE FOR GST IN FIGURES AND IN WORDS	REBATE @ 16.60%	
					UNIT IN FIGURES AND IN WORDS	AMOUNT
1	2	3	4	5	6	7
						1334262.65
35.2	895.65 Sq.M.	SPECIAL CEILING PLASTERING IN CEMENT MORTAR 1:3 (ONE OF CEMENT AND THREE OF CRUSHED STONE SAND) 10MM THICK FOR BOTTOM OF ROOF, STAIR, WAIST, LANDING AND SUNSHADES IN ALL FLOORS FINISHED WITH NEAT CEMENT INCLUDING HACKING THE AREAS, PROVIDING BAND CORNICE, SCAFFOLDING, CURING ETC., COMPLETE.	✓	Rs.250.00 (Rupees two hundred and fifty only)	1.Sq.M. (ONE SQUARE METRE)	223912.50
37.2	3120.15 Sq.M.	WHITE WASHING TWO COATS OF OLD WALL FOR OLD CEILING SURFACES BY USING CLEAN SHELL LIME SLAKED INCLUDING COST OF LIME, GUM, BLUE, BRUSHES INCLUDING SCAFFOLDING ETC., COMPLETE IN ALL RESPECTS AND COMPLYING WITH STANDARD SPECIFICATIONS.	✓	Rs.29.00 (Rupees twenty nine only)	1.Sq.M. (ONE SQUARE METRE)	90484.35
37.3	5965.75 Sq.M.	THOROUGH SCRAPPING OF OLD PLASTERED SURFACE ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS.	✓	Rs.3.50 (Rupees three and paise fifty only)	1.Sq.M. (ONE SQUARE METRE)	20880.13
38.4.3	7544.90 Sq.M.	PAINTING THE OLD WALLS WITH TWO COATS OF OIL BOUND DISTEMPER OVER EXISTING WALL SURFACES EXCLUDING THOROUGH SCRAPPING INCLUDING COST OF PAINTS, PUTTY, BRUSHES, WATERING, CURING, ETC., ALL COMPLETE AS DIRECTED BY THE DEPARTMENTAL OFFICERS (PAINTS AND ITS SHADE SHALL BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	✓	Rs.110.00 (Rupees one hundred and ten only)	1.Sq.M. (ONE SQUARE METRE)	829939.00
40.1	684.70 Sq.M.	TWO COATS OF PAINTING OVER THE OLD WOOD WORK WITH APPROVED FIRST-CLASS SYNTHETIC ENAMEL READY MIXED PAINT INCLUDING THOROUGH SCRAPPING ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS (THE QUALITY AND THE SHADE OF ENAMEL PAINT SHOULD BE GOT APPROVED BY THE EXECUTIVE ENGINEER BEFORE USE)	✓	Rs.144.00 (Rupees one hundred and forty four only)	1.Sq.M. (ONE SQUARE METRE)	98596.80
41.1	519.00 Sq.M.	TWO COATS OF PAINTING OVER THE OLD IRON WORK AND OTHER SIMILAR WORKS SUCH AS PVC / ASTM PIPES, KERB STONE AND GRILLS WITH APPROVED FIRST CLASS SYNTHETIC ENAMEL READY MIXED PAINT INCLUDING THOROUGH SCRAPPING ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS (THE QUALITY AND THE BRAND OF ENAMEL PAINT SHOULD BE GOT APPROVED BY THE EXECUTIVE ENGINEER BEFORE USE)	✓	Rs.125.00 (Rupees one hundred and twenty five only)	1.Sq.M. (ONE SQUARE METRE)	64875.00
41.3	273.50 Sq.M.	REMOVING OLD PAINT FROM IRON SURFACE WITH SAND PAPER ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS.	✓	Rs.7.00 (Rupees seven only)	1.Sq.M. (ONE SQUARE METRE)	1914.50
43.1	3.119 M.T.	SUPPLYING, FABRICATING AND PLACING IN POSITION OF MILD STEEL GRILLS/RIBBED TOR STEELS (WITHOUT CEMENT SLURRY) OF ALL DIAMETERS FOR REINFORCEMENT FOR ALL FLOORS INCLUDING COST OF BINDING WIRE, BENDING, TYING ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS FOR ALL SIZES.	✓	Rs.78400.00 (Rupees seventy eight thousand and four hundred only)	1 M.T. (ONE METRIC TONNE)	244529.60
						2909394.53

ITEM	QUANTITY	DESCRIPTION OF WORK	TNBP No.	RATE EXCLUSIVE FOR GST IN FIGURES AND IN WORDS	REBATE @ 16%	
					UNIT IN FIGURES AND IN WORDS	AMOUNT
1	2	3	4	5	6	7
						2909394.53
44.6	82.00 Rmt.	SUPPLYING AND FIXING OF 110MM DIA PVC SWR PIPE WITH ISI MARK CONFIRMING TO IS 13952:1992-TYPE 'A' FOR RAIN WATER DOWN FALL PIPE WITH RELEVANT SPECIALS SUCH AS GRATINGS, SHOES, BENDS, OFFSETS CONFIRMING TO IS 14735 INCLUDING JOINTING WITH SEAL RING CONFIRMING IS 5382 WITH LEAVING A GAP ABOUT 10MM TO ALLOW THERMAL EXPANSION WITH NECESSARY CLAMPS, TEAK WOOD PLUGS, ETC., OF APPROVED QUALITY AND INCLUDING FIXING C.I. GRATINGS AT THE JUNCTION OF PARAPET AND FLOOR OR ROOF SLAB ETC., INCLUDING FINISHING ETC., COMPLETE COMPLYING WITH RELEVANT STANDARD SPECIFICATIONS.	✓	Rs.320.00 (Rupees three hundred and twenty only)	1. Rmt. (ONE RUNNING METRE)	26240.00
51.1	4 NOS.	SUPPLYING AND ERECTION OF WHITE FRP/PPFRP SINTEX TRIPLE LAYER WATER TANK 750 LITRES CAPACITY , NEITHER CORRODE NOR RUST DUE TO THE EMPLOYMENT OF HIGH QUALITY MATERIAL, WHEREAS THE THREE LAYERS OF THE TANKS ARE UV STABILIZED AND CONTROL THE INSIDE TEMPERATURE OF THE WATER WITH TOP LID WITH PROVISIONS OF LOCKING INCLUDING NECESSARY SPECIALS AND FITTINGS FOR STORING POTABLE WATER AND MANUFACTURED WITH MATERIAL WHICH DO NOT IMPORT ANY TASTE /ODOUR/ANY TOXIC EFFECT AND NOT TO CONTAMINATE ETC WITH CARBON BLOCK CONTENT AND DISPERSION IN ACCORDANCE WITH RELEVANT SPECIFICATION AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS ETC. COMPLETE. (THE QUALITY OF THE WATER TANK SHOULD BE GOT APPROVED FROM THE EE BEFORE USE)	✓	Rs.6700.00 (Rupees six thousand and seven hundred only)	1.NO. (EACH)	26800.00
51.1.1	39 NOS.	SUPPLYING AND FIXING OF PVC WATER TANK COVER TO THE EXISTING PVC WATER TANK INCLUDING COST OF ALL MATERIALS AND LABOUR CHARGES ETC., ALL COMPLETE COMPLYING WITH RELEVANT STANDARD SPECIFICATIONS AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE QUALITY AND BRAND OF THE MATERIAL SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	✓	Rs.260.00 (Rupees two hundred and sixty only)	1.NO. (EACH)	10140.00
56.3.2	4 NOS.	SUPPLYING AND FIXING OF INDIAN WATER CLOSET WHITE GLAZED (ORIYA TYPE) OF SIZE 580MMX440MM OF APPROVED MAKE WITH ISI MARK (TO BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE) WITH PVC SWR GRADE P OR S TRAP INCLUDING CONCRETE PACKING, FILLING PORTION WITH EARTH, FLOORING THE AREA WITH 75MM THICK BRICK JELLY CONCRETE IN CC 1:8:16 (ONE OF CEMENT, EIGHT OF CRUSHED STONE SAND AND SIXTEEN OF BRICK JELLY) USING 40MM SIZE BRICK JELLY AND TOP LEFT ROUGH TO RECEIVE THE FLOOR PLASTERING BUT INCLUDING ANTISYPHONAGE CONNECTION, CURING, ETC. ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (IN GROUND FLOOR)	✓	Rs.3000.00 (Rupees three thousand only)	1.NO. (EACH)	12000.00
56.4.2	5 NOS.	SUPPLYING AND FIXING OF INDIAN WATER CLOSET WHITE GLAZED (ORIYA TYPE) OF SIZE 580MMX440MM OF APPROVED MAKE WITH ISI MARK (TO BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE) WITH PVC SWR GRADE P OR S TRAP INCLUDING CONCRETE FILLING THE SUNK PORTION WITH BRICK JELLY LIME CONCRETE PROPORTION OF BRICK JELLY TO LIME BEING 32:12½ BY VOLUME (32 CFT OF 20MM GAUGE BRICK JELLY AND 12 ½ CFT OF SLAKED LIME) (NO SAND) AND TOP 75MM THICK BRICK JELLY CONCRETE IN CC 1:8:16 (ONE OF CEMENT, EIGHT OF CRUSHED STONE SAND AND SIXTEEN OF	✓	Rs.4700.00 (Rupees four thousand and seven hundred only)	1.NO. (EACH)	23500.00
						3008074.53


CONTRACTOR


NO. OF CORRECTIONS


SUPERINTENDING ENGINEER/SOUTH CIRCLE.

					REBATE @ 16.60%	
ITEM NO	QUANTITY	DESCRIPTION OF WORK	TNBP No.	RATE EXCLUSIVE FOR GST IN FIGURES AND IN WORDS	UNIT IN FIGURES AND IN WORDS	AMOUNT
1	2	3	4	5	6	7
		BROKEN BRICK JELLY) USING 40MM SIZE BRICK JELLY INCLUDING PLASTERING THE SIDES OF SUNK PORTION IN CM 1:3 (ONE OF CEMENT AND THREE OF CRUSHED STONE SAND) 12MM THICK MIXED WITH WATER PROOFING COMPOUND AT 2KG/SQM AND TOP LEFT ROUGH TO RECEIVE THE FLOOR PLASTERING BUT INCLUDING ANTISYPHONAGE CONNECTION, ONE COAT OF BITUMEN FOR THE SIDES, BOTTOM AND CURING ETC., COMPLETE IN ALL FLOORS (OTHER THAN GROUND FLOOR)				3008074.53
58.3		SUPPLYING AND FIXING THE FOLLOWING DIA PVC (SWR) PIPE WITH ISI MARK CONFIRMING TO IS 13952:1992- TYPE 'B' FOR SOIL LINE WITH RELEVANT SPECIALS CONFIRMING TO IS 14735 INCLUDING JOINTING WITH SEAL RING CONFIRMING TO IS 5382 WITH LEAVING A GAP ABOUT 10MM TO ALLOW THERMAL EXPANSION, FIXING THE PIPES INTO WALLS WITH NECESSARY WOODEN PLUG, SCREWS, HOLDING WHEREVER NECESSARY AND MAKING GOOD OF THE DISMANTLED PORTION WITH NECESSARY CONNECTIONS TO SANITARY FITTINGS ETC., COMPLETE IN ALL RESPECTS AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS.				
	180.00 Rmt.	(a) 110MM DIA PVC SWR PIPE INCLUDING ALL REQUIRED PVC SPECIALS ETC., ALL COMPLETE.	✓	Rs.660.00 (Rupees six hundred and sixty only)	1.Rmt. (ONE RUNNING METRE)	118800.00
	153.00 Rmt.	(b) 75MM DIA PVC SWR PIPE INCLUDING ALL REQUIRED PVC SPECIALS ETC., ALL COMPLETE.	✓	Rs.540.00 (Rupees five hundred and forty only)	1.Rmt. (ONE RUNNING METRE)	82620.00
64.1.2		WIRING WITH 1.5 SQMM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1 K.V. GRADE CABLE WITH CONTINUOUS EARTH BY MEANS OF 1.5 SQMM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1 K.V. GRADE CABLE FOR OPEN WIRING WITH PVC RIGID CONDUIT PIPE HEAVY DUTY WITH ISI MARK WITH SUITABLE SPECIALS, TW BOX OF SIZE 100X100X63 MM AND JUNCTION BOX OF SIZE 150X150X63MM, TW ROUND BLOCK PVC BENDS, TEES, JUNCTION BOXES, TW PLUGS, BRASS SCREWS ETC., CONTROLLED BY 5 AMPS FLUSH TYPE SWITCH INCLUDING CIRCUIT MAINS COST OF ALL MATERIALS, SPECIALS ETC., ALL COMPLETE. (OPEN WIRING)				
	70 POINTS	(a) LIGHT POINT WITH CEILING ROSE	✓	Rs.725.00 (Rupees seven hundred and twenty five only)	1 POINT (EACH POINT)	50750.00
	30 POINTS	(b) LIGHT POINT WITHOUT CEILING ROSE	✓	Rs.760.00 (Rupees seven hundred and sixty only)	1 POINT (EACH POINT)	22800.00
64.1.3	43 POINTS	SUPPLYING AND FIXING OF CALL BELL / BUZZER 6MM SUITABLE FOR AC / DC ETC. , ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE QUALITY AND BRAND OF THE MATERIALS SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	✓	Rs.100.00 (Rupees one hundred only)	1 POINT (EACH POINT)	4300.00
						3287344.53

REBATE @ 16.60%						
ITEM	QUANTITY	DESCRIPTION OF WORK	TNBP No.	RATE EXCLUSIVE FOR GST IN FIGURES AND IN WORDS	UNIT IN FIGURES AND IN WORDS	AMOUNT
1	2	3	4	5	6	7
						3287344.53
65.1	11 POINTS	WIRING WITH 1.5 SQMM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1 K.V. GRADE CABLE WITH CONTINUOUS EARTH BY MEANS OF 1.5 SQMM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1 K.V. GRADE CABLE IN FULLY CONCEALED PVC RIGID CONDUIT PIPE HEAVY DUTY WITH ISI MARK WITH SUITABLE SIZE MS BOX OF 16G THICK CONCEALED AND COVERED WITH 3MM THICK LAMINATED HYLEM SHEET FOR FAN POINT CONTROLLED BY 5 AMPS FLUSH TYPE SWITCH INCLUDING CIRCUIT MAINS, COST OF ALL MATERIALS, SPECIALS, ETC., ALL COMPLETE.	✓	Rs.1560.00 (Rupees one thousand five hundred and sixty only)	1 POINT (EACH POINT)	17160.00
67.1	43 POINTS	WIRING WITH 1.5 SQMM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1 K.V. GRADE CABLE WITH CONTINUOUS EARTH BY MEANS OF 1.5 SQMM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1 K.V. GRADE CABLE IN FULLY CONCEALED PVC RIGID CONDUIT PIPE HEAVY DUTY WITH ISI MARK WITH SUITABLE SIZE MS BOX OF 16G THICK CONCEALED AND COVERED WITH 3MM THICK LAMINATED HYLEM SHEET FOR 5 AMPS 5 PIN PLUG SOCKET POINT AT SWITCH BOARD ITSELF INCLUDING CIRCUIT MAINS, COST OF ALL MATERIALS, SPECIALS, ETC., ALL COMPLETE.	✓	Rs.700.00 (Rupees seven hundred only)	1 POINT (EACH POINT)	30100.00
68.2.2	33 POINTS	WIRING WITH 1.5 SQMM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1 K.V. GRADE CABLE WITH CONTINUOUS EARTH BY MEANS OF 1.5 SQMM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1 K.V. GRADE CABLE FOR OPEN WIRING WITH PVC RIGID CONDUIT PIPE HEAVY DUTY WITH ISI MARK WITH SUITABLE SPECIALS, TW BOX OF SIZE 100X100X63 MM AND JUNCTION BOX OF SIZE 150X150X63MM, TW ROUND BLOCK PVC BENDS, TEES, JUNCTION BOXES, TW PLUGS, BRASS SCREWS ETC., FOR 5 AMPS 5 PIN PLUG SOCKET POINT AT CONVENIENT PLACES INCLUDING CIRCUIT MAINS COST OF ALL MATERIALS, SPECIALS ETC., ALL COMPLETE (OPEN WIRING)	✓	Rs.650.00 (Rupees six hundred and fifty only)	1 POINT (EACH POINT)	21450.00
70.1.1	18 NOS.	SUPPLYING AND FIXING OF WATER TIGHT BULK HEAD FITTING WITH GUARD SUITABLE FOR LED LAMP INCLUDING NECESSARY CONNECTIONS, COST OF MATERIALS ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS (THE QUALITY OF THE BULK HEAD FITTINGS SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	✓	Rs.480.00 (Rupees four hundred and eighty only)	1.NO. (EACH)	8640.00
75.1.2		SUPPLYING AND DELIVERY OF FOLLOWING ELECTRIC CEILING FAN WITH ISI MARK WITH BLADES AND DOUBLE BALL BEARING, CAPACITOR, ETC., COMPLETE WITH 300MM DOWN ROD, CANOPIES, CAPACITOR, SHACKLE BLADES WITH ELECTRONIC DIMMER SUITABLE FOR OPERATION ON 230 VOLTS 50 HTZ SINGLE PHASE AC SUPPLY CONFORMING TO ISS NO.374/79 AND PROVIDED WITH INSULATION. (THE BRAND SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE SUPPLY MADE).				
						3364694.53

CONTRACTOR

NO. OF CORRECTIONS

SUPERINTENDING ENGINEER/SOUTH CIRCLE

ITEM	QUANTITY	DESCRIPTION OF WORK	TNBP No.	RATE EXCLUSIVE FOR GST IN FIGURES AND IN WORDS	REBATE @ 16.60%	
					UNIT IN FIGURES AND IN WORDS	AMOUNT
1	2	3	4	5	6	7
	46 NOS.	(a) 48" ELECTRIC FAN 1200MM SWEEP	✓	Rs.1600.00 (Rupees one thousand and six hundred only)	1.NO. (EACH)	3364694.53 73600.00
77.5.1	250.00 Rmt.	RUN OFF MAIN WITH 2 WIRES OF 1.5 SQ.MM. PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1 KV GRADE CABLE WITH CONTINUOUS EARTH BY MEANS OF 1.5 SQ.MM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1. K.V. GRADE CABLE FOR OPEN WIRING WITH 19MM/20MM DIA RIGID PVC CONDUIT PIPE HEAVY DUTY WITH ISI MARK COST OF ALL MATERIALS, SPECIALS ETC., ALL COMPLETE.	✓	Rs.120.00 (Rupees one hundred and twenty only)	1.Rmt. (ONE RUNNING METRE)	30000.00
77.7.1	300.00 Rmt.	RUN OFF MAIN WITH 2 WIRES OF 2.5 SQ.MM. PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1 KV GRADE CABLE WITH CONTINUOUS EARTH BY MEANS OF 2.5 SQ.MM PVC INSULATED SINGLE CORE MULTI STRAND FIRE RETARDANT FLEXIBLE COPPER CABLE WITH ISI MARK CONFORMING TO IS: 694/1990, 1.1. K.V. GRADE CABLE FOR OPEN WIRING WITH 19MM/20MM DIA RIGID PVC CONDUIT PIPE HEAVY DUTY WITH ISI MARK COST OF ALL MATERIALS, SPECIALS ETC., ALL COMPLETE.	✓	Rs.135.00 (Rupees one hundred and thirty five only)	1.Rmt. (ONE RUNNING METRE)	40500.00
100	173 NOS.	SUPPLYING AND FIXING OF 9 WATTS LED BULB OF BEST QUALITY INCLUDING COST OF MATERIAL AND FIXING ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE QUALITY OF THE 9 W LED LAMP SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	✓	Rs.130.00 (Rupees one hundred and thirty only)	1.NO. (EACH)	22490.00
101	10 NOS.	SUPPLYING AND FIXING OF 25 WATTS BULB WITH STREET LIGHT FITTINGS ARRANGEMENTS INCLUDING COST OF MATERIALS LABOUR CHARGES FOR FIXING OF LED STREET LIGHT FITTING ETC ALL COMPLETE AS PER RELEVANT STANDARD SPECIFICATION AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE QUALITY OF THE 25 WATTS LED LAMP WITH STREET LIGHT FITTINGS SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	✓	Rs.3200.00 (Rupees three thousand and two hundred only)	1.NO. (EACH)	32000.00
102	90 NOS.	SUPPLYING AND FIXING OF 4'18 WATTS CRYSTAL LED TUBE LIGHT AND FIXING THE TUBE LIGHT FITTINGS ON TEAK WOOD ROUND BLOCKS OF 75MM DIA OR 40MM DEEP SUSPENDED FROM CEILING OR MOUNTED ON THE WALL INCLUDING COST OF ALL MATERIALS AND LABOUR FOR FIXING IN POSITION ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE ENTIRE TUBE LIGHT FITTINGS SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	✓	Rs.500.00 (Rupees five hundred only)	1.NO. (EACH)	45000.00
104	18 NOS.	SUPPLYING AND FIXING OF 12 WATTS LED LAMP FOR BULK HEAD FITTINGS OF BEST QUALITY INCLUDING COST OF MATERIAL AND FIXING ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE QUALITY OF THE 12 WATTS LED LAMP SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	✓	Rs.170.00 (Rupees one hundred and seventy only)	1.NO. (EACH)	3060.00
						3611344.53

CONTRACTOR

NO. OF CORRECTIONS

SUPERINTENDING ENGINEER/SOUTH CIRCLE.

