Tamil Nadu Police Housing Corporation Limited (A Government of Tamil Nadu Undertaking) (An ISO 9001: 2015 Certified Company) No. 132, E. V. R. Salai, Kilpauk, Chennai – 600 010

Lr. No. CE / Plg/SP & COP Resi/2023

Dated: 21.06.2023

To

The Director General of Police, Head of Police Force, Tamil Nadu, Chennai – 600 004.

Sir,

Sub: TNPHC – Construction of SP camp office cum residence in Chengalpet, Tenkasi, Thirupathur, Ranipet and Kallakurichi District and construction of COP camp office cum residence in Tiruppur City – Rough cost estimates sent –Concurrence – Requested - Regarding.

__

The rough cost estimate proposals for the construction of SP camp office cum residence in Chengalpet, Tenkasi, Thirupathur, Ranipet and Kallakurichi District and construction of COP camp office cum residence in Tiruppur City are enclosed herewith.

2) The estimate are prepared based on the PWD plinth area of rates for the year 2023-2024 including all over head charges and the total estimate value arrives to ₹ 1300.00 lakhs as detailed below.

SI. No.	Name of Work	Amount ₹in lakhs	Remarks			
1.	Construction of Superintendent of Police Camp office cum residence at Chengalpet in Chengalpet District	200.00	> The land is identified in Block No. 27, Ward No. 5, T.S. No.1/1, Sub (division) survey No. 1/6, Chengalpet Taluk in Chengalpet District. > Necessary enterupon permission was issued by the District Collector/ Chengalpet District. Name transfer to Police Department is under process vide Proc.No.11014/2020/ஆ3, Dt: 07.12.2020. > The Land is sufficient for construction of			

				Superintendent of Police Camp office Cum
				Residence building. The location of the
				land is at the bottom of the Hill and the
				soil is moorum. Also the land is
				slopped. Hence provision for Retaining wall
				has been made so as to avoid soil erosion
				from the slopping area.
7				> The land is feasible for construction of
				SP camp office cum Residence at
				Chengalpet in Chengalpet District.
-				> The land is identified in S.No. 84 to an
				extent of 3 Acres at Ayikudi, Vellakkal
				Poththai, Kadayanallur Taluk in Tenkasi
1				District.
		Construction of		> The identified land along with proper way to
1		Superintendent of Police		be transferred in the Name of Police
	2	Camp office cum residence	200.00	Department and the same is under process
		at Vellakaal Poththai in		by the SP/Tenkasi vide
		Tenkasi District.		Lr.No.K5/22961/2021, Dt: 01.06.2023.
				> The site is feasible to construct SP camp
				office cum residence on obtaining
				approach road to Police Department.
	Je II			> The land is identified in S.No. 486/3 to an
		The will will also oil be		extent of 1.98.5 Hectare (or) 4.99 Acres at
		Construction of		Adhiyur Village in Thirupathur District and
		Superintendent of Police		land is classified as Punjai land.
	3	Camp office cum residence	200.00	> Enter-upon permission obtained from the
		at Adhiyur in Thirupathur		District Collector/ Thirupathur vide
		District.		Proc.No.ஆ2-5692/2022, Dt: 31.05.2022.
		William Park Carlot Ball		A CD comm
-		the many than the same		The site is feasible to construct SP camp office cum residence.
-	-			> The land is identified in S.No.639/1, Ward A,
		Construction	Sensitive Co.	Block – 24, at Ranipet in Karai Village
		Construction of	200.00	alloted to AR Police land with total extent of
	1	Superintendent of Police Camp office cum residence		8.06 Acre in which 1.50 Acres have to be
	4			sub divided for the SP Camp office cum
		at Ranipet in Ranipet	Mar 1	residence building.
		District.	13,41	> The site is located adjacent to Ranipet-
				Chittur main road at Karai Village.


-				
				The site is in low lying area of about 1.2mt
				depth from the existing Cement Concrete
				road. Hence it is necessary to provide gravel
				filling around the scheme area.
				The site is feasible to construct SP camp office cum residence .
			>	The land suggested by the user department
	Construction of			in S.No.179, Melvizhi is belongs to sarkar
				poromboke and (forest in remark column)
				with an extent of 15.85 acres.
			>	The land belongs to Revenue
	Superintendent of Police			Department. However now the land is
5	Camp office cum residence at Melvizhi in Kallakurichi District.	200.00		in the control of Forest Department.
				Enterupon permission to be obtained
4 "				from Revenue Department.
				The land is feasible to construct SP camp
			Ĺ	office cum residence on Name transfer of
				land to Police Department.
			A	The land is identified in T.S.No. 3/4 located
	Construction of Commissioner of Police Camp office cum Residence in Tiruppur City.	300.00		in Tiruppur Avinashi State High way
				opposite to Collector Bungalow to an extent
6				of 2.25 Acres.
			2	The land belongs to Police Department.
			>	The land is feasible for construction of
				new COP camp office cum residence.
	Total	1300.00		
			1	

3) Therefore it is requested that necessary concurrence may be issued for the construction of SP camp office cum residence in Chengalpet, Tenkasi, Thirupathur, Ranipet and Kallakurichi District and construction of COP camp office cum residence in Tiruppur City by utilizing the overall savings available in TNPHC.

Encl: As Stated.

Yours faithfully,

Chairman and Managing Director



TIRUPATHUR SUB DIVISION

Name of work: Construction of Superintendent of Police Camp office cum Residence Building at Adhiyur in Thirupathur District.

Rough Cost Estimate for Residential building - Framed Structure

Area statement

Name of Building	GF	FF	Total	Head Room	Portico
Superintendent of Police Camp office cum Residence Building	168.74	130.34	299.08	13.89	16.09
Total	168.74	130.34	299.08	13.89	16.09

AS PER PWD PLINTH AREA RATES 2023-2024

Sl.No	Description	Plinth Area	Rate	Per	Amount
1	Foundation	168.74	5350.00	m ²	902759.00
2	Additional basement height 0.90m height (3x523)	168.74	1569.00	m ²	264753.06
3	Super Structure (Framed Structure)				
	Super Structure in Ground Floor	168.74	14850.00	m ²	2505789.00
	Super Structure in First Floor (FF + Sit out half area = 63.35+11.90)	130.34	14891.00	m ²	1940892.94
4	Portico (65% of plinth area of residential cost) (Excluding verandah & Wash)	32.18	9652.50	m^2	310617.45
5	Head room (65% of plinth area of residential cost)	13.89	9679.15	m ²	134443.39
6	Roof Finishing	168.74	1820.00	m ²	307106.80
7	Anti termite treatment	168.74	130.00	m ²	21936.20
8	Double charged Vitrified tiles (800x800x10mm) floor finishing (Total PA 80%)	239.26	2065.00	m ²	494080.16
9	Cement painting /OBD for Inner 50% of(Total Area + Head room)	156.49	587.00	m ²	91856.70
10	Exterior Emulsion painting for Outer 50% of(Total Area + Head room)	156.49	867.00	m ²	135672.50
11	Provision for Joineries (80% of Total area + Head Room)	250.38	614.00	m ²	153730.86
12	Provision for dummy column arrangements	130.34	561.00	m ²	73120.74
13	False Ceiling with plain Gypsum board. (camp office = 4.905*3.635=17.83, Office = 4.905*4.26= 20.90)	38.73	1303.00	m ²	50465.19

60	Description	Plinth Area	Rate	Per	Amount
34	Provision non ductable A.C Units (Office = 4.905*4.26= 20.90)	20.90	6110.00	m²	127699.00
15	Internal Water supply arrangements	299.08	717.00	m ²	214440.36
16	Internal Sanitary arrangements	299.08	558.00	m ²	166886.64
17	Internal Electrical arrangements	299.08	1175.00	m ²	351419.00
18	Internal Electrical arrangements add Extra for Provision of LED lighting, Computer Plugs and Power Plugs =170+20.45+27.60=218.05)		218.05	m²	65214.39
19	UPVC Window (80% of Total area + Head Room)	250.38	1942.00	m ²	486230.19
20	Extra provision for TW door shutters, cupboard shutters, bath room fittings & electrical fittings (80%)	250.38	1980.00	m ²	495744.48
	BUILDING COST - Sub Total -	I		Rs:	9294858.05
21	Newly developed external Water supply arrangements (GF+FF)	299.08	860.00	m²	257208.80
22	Newly developed external Sanitary arrangements (GF+FF)	299.08	266.00	m ²	79555.28
23	Newly developed external Electrical arrangements (GF +FF)	299.08	787.00	m ²	235375.96
24	Rain water Harvesting	4.00	16440.00	m ²	65760.00
25	Pavement platform alround 1.20 m width	65.75	1210.00	Rmt	79557.50
26	Approach road	945.00	841.00	m ²	794745.00
27	Provision for Compound wall (Approximate 1Acres)	250.00	7500.00	Rmt	1875000.00
28	Soil Investigation charges	1.00	38705.00	Nos	38705.00
29	Provision for Cutting and filling levelling area (Approximate 1 Acres)			LS	300000.00
30	Provision for Deep Borewell and pumpset arrangements			LS	400000.00
31	Provision for Strom water drain and sullage drain			LS	230000.00
32	Provision for Culvert			LS	200000.00
33	Provision for Sump and Pump room			LS	400000.00
34	Provision for local body water supply connection.			LS	50000.00
35	Provision for Lettering and numbering arrangements			LS	30000.00
36	Provision for avenue trees			LS	25000.00
37	Elevation at 1% of Building Cost			As per PWD Norms	92948.58
	SUB - TOTAL - I	п			14448714.17

*

-6	Description	Plinth Area	Rate	Per	Amount
100	GST @ 18%			LS	2600768.55
•	SUB - TOTAL - II				17049482.73
39	Labour Welfare fund @ 1.00%			LS	170494.83
40	Unforeseen items & Petty Supervision charges,contingencies @ 2.50%			LS	426237.07
41	Supervision Charges @ 7.50%			LS	1278711.20
42	Price adjustment clause @ 5%			LS	852474.14
	SUB - TOTAL - IV				19777399.96
43	Foundation stone laying and Inagural function.	V		LS	13000.00
44	Advertisement charges			LS	50000.00
45	Provision for EB Deposit & Development Charges			LS	50000.00
46	Payment to Local Body and Planning clearence			LS	50000.00
47	Provision for Structural Design & Consultancy charges			LS	50000.00
	Grand Total Rs				19990399.96
		Say Rs.	200.00 Lakhs		

Junior Engineer
TP+

Asst. Executive Engineer

Executive Engineer

N Solan DIVISO

Superintendent-of Police,
Tirupasiur District.

MW 106/23

SETTIE .

CE MPH